

AD A090132

LEVEL III

(12)

F

DNA 5278F ✓

COST ASSESSMENT FOR SHIELDING OF C³ TYPE FACILITIES

IIT Research Institute
10 West 35th Street
Chicago, Illinois 60616

DTIC
OCT 9 1980
C

1 March 1980

Final Report for Period 29 January 1979—29 February 1980

CONTRACT No. DNA 001-79-C-C205

APPROVED FOR PUBLIC RELEASE;
DISTRIBUTION UNLIMITED.


THIS WORK SPONSORED BY THE DEFENSE NUCLEAR AGENCY
UNDER RDT&E RMSS CODES B363079464 099QAXCC30101 H2590D
AND B363079464 099QAXCC30102 H2590D.

Prepared for
Director
DEFENSE NUCLEAR AGENCY
Washington, D. C. 20305

DDC FILE COPY

80 10 9 030

DISCLAIMER NOTICE



THIS DOCUMENT IS BEST QUALITY AVAILABLE. THE COPY FURNISHED TO DTIC CONTAINED A SIGNIFICANT NUMBER OF PAGES WHICH DO NOT REPRODUCE LEGIBLY.

**BLANK PAGES
IN THIS
DOCUMENT
WERE NOT
FILMED**

Destroy this report when it is no longer
needed. Do not return to sender.

PLEASE NOTIFY THE DEFENSE NUCLEAR AGENCY,
ATTN: STTI, WASHINGTON, D.C. 20305, IF
YOUR ADDRESS IS INCORRECT, IF YOU WISH TO
BE DELETED FROM THE DISTRIBUTION LIST, OR
IF THE ADDRESSEE IS NO LONGER EMPLOYED BY
YOUR ORGANIZATION.



UNCLASSIFIED

SECURITY CLASSIFICATION OF THIS PAGE (When Data Entered)

REPORT DOCUMENTATION PAGE		READ INSTRUCTIONS BEFORE COMPLETING FORM
1. REPORT NUMBER DNA 5278F	2. GOVT ACCESSION NO. AD-A090132	3. RECIPIENT'S CATALOG NUMBER
4. TITLE (and Subtitle) COST ASSESSMENT FOR SHIELDING OF C ³ TYPE FACILITIES	5. TYPE OF REPORT & PERIOD COVERED Final Report, for Period 29 Jan 79-29 Feb 80	6. PERFORMING ORG. REPORT NUMBER IITRI Project E6465
7. AUTHOR(s) L. Valcik	8. CONTRACT OR GRANT NUMBER(s) DNA 001-79-C-0205 / NEW	
9. PERFORMING ORGANIZATION NAME AND ADDRESS IIT Research Institute 10 West 35th Street Chicago, Illinois 60616	10. PROGRAM ELEMENT, PROJECT, TASK AREA & WORK UNIT NUMBERS Subtasks 099QAXCC301-01 and 099QAXCC301-02	
11. CONTROLLING OFFICE NAME AND ADDRESS Director Defense Nuclear Agency Washington, D.C. 20305	12. REPORT DATE 1 March 1980	13. NUMBER OF PAGES 112
14. MONITORING AGENCY NAME & ADDRESS (if different from Controlling Office) 099496 11C304	15. SECURITY CLASS (of this report) UNCLASSIFIED	15a. DECLASSIFICATION/DOWNGRADING SCHEDULE
16. DISTRIBUTION STATEMENT (of this Report) Approved for public release; distribution unlimited.		
17. DISTRIBUTION STATEMENT (of the abstract entered in Block 20, if different from Report)		
18. SUPPLEMENTARY NOTES This work sponsored by the Defense Nuclear Agency under RDT&E RMSS Codes B363079464 099QAXCC30101 H2590D and B363079464 099QAXCC30102 H2590D.		
19. KEY WORDS (Continue on reverse side if necessary and identify by block number) EMP Shielding Welded Shield Riveted Shield Powder-Driven Pins Arc Sprayed Zinc Cost Assessment		
20. ABSTRACT (Continue on reverse side if necessary and identify by block number) Costs were estimated for four slightly different designs for an all-welded steel envelope shield to protect a C ³ facility against high-altitude EMP, and for an alternative shield design using overlapping steel sheets joined by powder-driven pins and with seams arc sprayed with zinc. The all-welded shields are substantially more expensive because of the high cost of MIG welding.		

DD FORM 1 JAN 73 1473


EDITION OF 1 NOV 65 IS OBSOLETE

UNCLASSIFIED

SECURITY CLASSIFICATION OF THIS PAGE (When Data Entered)

UNCLASSIFIED

SECURITY CLASSIFICATION OF THIS PAGE(When Data Entered)



UNCLASSIFIED

SECURITY CLASSIFICATION OF THIS PAGE(When Data Entered)

SUMMARY

The purpose of this program was to assess the costs of providing all-welded steel envelope shields to protect C³ facilities from the EMP effect of high-altitude nuclear detonations. Costs were to be developed for three levels of shielding -- 30, 60, and 100 dB -- both for new construction and for shield retrofit to an existing building. For purposes of estimating costs to shield a C³ facility, a building size of 60 feet wide by 200 feet long by 20 feet high was assumed in all cases.

Baseline facility requirements, electrical design of the shield, and cost estimates for shield quality control were developed by IIT Research Institute. Baseline utilities design requirements, mechanical design of the welded shields, and cost estimates for the welded shield implementations were provided by L. B. Knight & Associates, Chicago, IL, an architectural and engineering firm acting as consultant and subcontractor to IITRI. Subsequently, IITRI developed a design outline and a rough cost estimate for a shield fastened by powder-driven pins instead of welding.

The practical limitations and relative costs for MIG welding of steel sheets in the field resulted in the choice of 11 ga (0.12 inch) material for all the welded shields. This thickness is more than adequate to provide a shielding effectiveness of 100 dB based on absorption loss within the material. Consequently, separate designs were not developed for 30 dB and 60 dB all-welded shields. The actual shielding effectiveness of a shield of this thickness would depend on seam imperfections and on penetrations. Long-conductor penetrants are assumed to enter the building through a one-quarter-inch thick entry plate and a shielded entry vault.

Four basic shield configurations were studied:

- I External shield for a new building
- II Internal shield for a new building
- III Internal shield retrofit for an existing building
(existing internal walls/partitions removed and replaced)
- IV Internal shield retrofit for an existing building
(existing internal walls retained)

Building construction of poured-in-place concrete was assumed for these four conditions. Two additional conditions, IIIA and IVA, were assumed for existing buildings with concrete block exterior walls.

Accession For	<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
	NTIS GRA&I		
DTIC TAB			
Unannounced			
Justification			
By			
Distribution/			
Availability Codes			
Avail and/or			
Dist Special			
			A

Costs for shield construction and quality assurance for Conditions I and II are estimated to be slightly greater than \$1,000,000. For Conditions III and IIIA, shield costs are approximately 50 percent greater, and for Conditions IV and IVA, approximately twice as great. A very substantial portion of the costs for all these configurations is due to the high cost of MIG welding of the shield seams.

As an alternative to an all-welded shield, a design was considered using overlapping sheets which are fastened together mechanically, as well as fastened to the inner surface of the building, using powder-driven pins (Condition V). Since welding of these sheets is not required, thinner material can be used (14 ga or 18 ga). Seams would be arc sprayed with zinc for good electrical continuity. The welded one-quarter-inch entry plate is still retained. The cost for this design was roughly estimated as \$525,000 -- about half that for Condition II (all welded).

In comparing the costs of providing a shielded C³ building, it may be desirable to include the cost of the building, especially if a new building is to be constructed (Conditions I, II, and V). In this case the costs for Conditions I, II, and III are comparable (within about 10 percent), Condition IV is approximately 30 percent more costly, and Condition V is approximately 35 percent less costly.

Table 10, Section 9 presents a summary of the costs associated with each configuration and/or option.

While the design for Condition V appears to be very attractive economically, no experimental evidence is available regarding the shielding effectiveness of a facility of this type. Also, the practicality of this type of construction for the floor shield is uncertain due to the resulting surface roughness caused by the pin heads, and also due to uncertainty of the long term integrity of the arc-sprayed zinc seams under heavy or varying weight loads. If a welded 11 ga floor shield were required, the cost would increase approximately \$100,000.

CONTENTS

SUMMARY	1
LIST OF ILLUSTRATIONS	6
LIST OF TABLES	8
1 INTRODUCTION	9
1.1 General	9
1.2 Description of Program	9
1.2.1 Purpose	9
1.2.2 Procedure	10
1.3 Organization of the Report	10
2 BASELINE DESIGN OF C ³ FACILITY	11
2.1 Facility Requirements	11
2.2 Basic Architectural and Structural Design	11
2.3 Utilities Descriptions	13
2.3.1 Heating, Ventilating, and Air Conditioning	13
2.3.2 Electrical	15
2.3.3 Plumbing/Fire Protection	18
3 ELECTRICAL DESIGN FOR SHIELDS	20
3.1 Introduction	20
3.2 Shielding Requirements	20
3.2.1 Plane Wave Incident on Infinite Flat Sheet	20
3.2.2 Corner Effects	21
3.2.3 Currents from Penetrants	21
3.2.4 Numerical Examples	23
3.3 Design Approach	23
3.3.1 Design Assuming Linear Behavior of Shield	23
3.3.2 Effect of Magnetic Saturation on Shield Design	28
3.4 Specific Shield Configurations	33

4	MECHANICAL DESIGN FOR WELDED SHIELDS	36
4.1	General	36
4.1.1	Envelope Shield	36
4.1.2	Penetrations	41
4.2	Condition I, New Construction, External Shield	46
4.3	Condition II, New Construction, Internal Shield	50
4.4	Condition III and IIIA, Retrofit Construction, Internal Shield, Interior Walls Replaced	56
4.5	Conditions IV and IVA, Retrofit Construction, Internal Shield, Interior Walls Retained	61
5	COST ESTIMATES FOR WELDED SHIELDS	66
6	DESIGN FOR SHIELD FASTENED BY POWDER-DRIVEN PINS	70
6.1	Introduction	70
6.2	General Description	70
6.3	Some Characteristics of Powder-Driven Pins	72
6.4	Grit Blasting	73
6.5	Zinc Arc Spraying	73
6.6	Problems Associated With This Shield Design	74
7	COST ESTIMATE FOR SHIELD FASTENED BY POWDER-DRIVEN PINS	75
7.1	Galvanized Steel Sheet	75
7.2	Fastening Pins	77
7.3	Grit Blasting of Seams	77
7.4	Shielded Doors	77
7.5	Zinc Arc Spraying	77
7.6	Ceiling Hangers	77
7.7	Plate, 1/4 Inch	78
7.8	Penetrations	78
8	SHIELD QUALITY CONTROL, EFFECTIVENESS TESTS, AND MAINTENANCE COSTS . .	79
8.1	Introduction	79
8.2	Quality Control During Construction	79
8.2.1	Testing of Steel Samples	79
8.2.2	Floor Plates at Perimeter Wall	79
8.2.3	Seams, Plug Welds, and Conductor Penetrations	80

8.3	Initial Performance Certification	80
8.3.1	SELDS Testing	80
8.3.2	Small-Antenna Radiation Testing	82
8.3.3	Outline of Certification Test Program	83
8.4	Periodic Inspection and Maintenance	84
8.5	Total Costs for Shield Quality Assurance and Maintenance	84
9	CONCLUSIONS AND RECOMMENDATIONS	86
10	REFERENCES	90

APPENDICES

A	FACTORS AFFECTING THE OPINIONS OF PROBABLE COST FOR THE ALL-WELDED SHIELD DESIGNS	91
B	DETAILED LISTS OF SHIELD CONSTRUCTION COSTS	95

ILLUSTRATIONS

1	Architectural/Structural Floor Plan	12
2	HVAC Plan; Wall Penetrations	14
3	HVAC Plan; Roof Penetrations	16
4	Electrical Plan; Wall/Roof Penetrations	17
5	Plumbing Plan; Floor Penetrations	19
6	Shielding Degradation near Corners in a Shielded Space	22
7	Planar Absorption Loss at $f = 10$ kHz	26
8	Approximation of Nonlinear Magnetization Curve	29
9	Magnetic Field in Steel Plate	29
10	Minimum Thickness of Steel Shield for 120 dB Absorption Loss	34
11	Typical Shielded Entry Box (for 30 dB Shielding)	37
12	Arrangements of Welded Shield Plates on Walls	39
13	Typical Shielding Plan for Floor and Ceiling	40
14	Typical Shielded Door	42
15	Typical Penetration Details for Intake/Exhaust Duct	43
16	Typical Penetration Details for Pipe/Conduit	44
17	Typical Penetration Details for Floor Drain	45
18	Condition I Shielding Plan	47
19	Condition I Shielding Isometric	48
20	Condition I Vertical Wall Detail	49
21	Condition I Horizontal Wall Detail	51
22	Condition II Shielding Plan	52
23	Condition II Shielding Isometric	53

24	Condition II Vertical Wall Detail	54
25	Condition II Horizontal Wall Detail	55
26	Condition III/IIIA Shielding Plan	57
27	Condition III/IIIA Shielding Isometric	58
28	Condition III/IIIA Vertical Wall Detail	59
29	Condition III/IIIA Horizontal Wall Detail	60
30	Condition IV/IVA Shielding Plan	62
31	Condition IV/IVA Shielding Isometric	63
32	Condition IV/IVA Vertical Wall Detail	64
33	Condition IV/IVA Horizontal Wall Detail	65
34	Shield Design for Condition V	71
35	Placement of Feedwires for SELDS Testing of Shielded Facility . . .	81

TABLES

1	Standard Thickness of Metal Sheets	27
2	Opinion of Probable Cost; Condition I	67
3	Opinion of Probable Cost; Condition II	67
4	Opinion of Probable Cost; Condition III	68
5	Opinion of Probable Cost; Condition IIIA	68
6	Opinion of Probable Cost; Condition IV	69
7	Opinion of Probable Cost; Condition IVA	69
8	Cost Estimate for Condition V	76
9	Costs for Shield Quality Control, Testing, and Maintenance	85
10	Comparison of Shielding Cost Estimates	87

SECTION 1

INTRODUCTION

1.1 GENERAL

This is the Final Report on Tasks I, II, III, and IV of Contract DNA 001-79-C-0205, and is concerned with the development of cost estimates for shielding command, control, and communications (C³) type facilities against electromagnetic pulse (EMP) radiation from high-altitude nuclear detonations. These four tasks consisted of:

- (1) Establishing baseline requirements
- (2) Electrical design of shield
- (3) Mechanical design of shield
- (4) Estimation of cost and ease of implementation.

This work was performed for the Defense Nuclear Agency, Washington, DC and was under the direction of Capt. Mike King (VLIS).

1.2 DESCRIPTION OF PROGRAM

1.2.1 Purpose

The purpose of the program was to provide electrical and mechanical concept design of envelope shielding alternatives to meet specified EMP field attenuation requirements, and to provide budgetary cost estimates for implementing these designs. The required shield designs are for an entire C³ facility, i.e., a building, and not for individual shields for the equipments and systems within a facility. The various all-welded shield configurations considered were:

- New building construction; external shield
- New building construction; internal shield
- Retrofit construction with interior (room) walls removed and replaced; internal shield
- Retrofit construction with interior (room) walls retained; internal shield.

It was the intent of the program to determine designs and cost estimates for welded shields providing 30, 60, and 100 dB shielding levels. However, as will be pointed out in the report, a limitation on the minimum gauge of steel sheet which can be welded in the field resulted in a welded design of 100 dB only. Use of powder-driven pins, instead of welding, to fasten the shield could permit use of thinner sheets, and a preliminary design is presented for this case.

1.2.2 Procedure

The program was conducted by IIT Research Institute and by L. B. Knight & Associates, Inc., an architectural and engineering firm acting as a consultant and subcontractor to IITRI. IITRI was responsible for determining the general baseline facility requirements, electrical design of the shield, and shielding effectiveness validation and maintenance requirements. Knight was responsible for baseline utilities design requirements, the mechanical design of the welded shields, and estimating the cost and ease of the welded shield implementation. IITRI developed a design outline and a rough cost estimate for a thinner shield fastened by powder-driven pins instead of welding.

1.3 ORGANIZATION OF THE REPORT

Section 2 of the report presents the baseline design, including the assumed facility requirements, a floor plan of a building accommodating the functions typically required of a C³ facility, and a general description of the required utilities.

Section 3 presents the electrical designs of the welded shields. Initially, the shielding requirements are discussed, followed by the design approach. First, linear behavior of the steel shield is assumed; then the effects of magnetic saturation are considered. Five shield configurations are listed.

Section 4 provides mechanical details of the welded shield construction. First, features common to each of the four configurations are given, followed by the construction details for the four individual configurations.

Section 5 presents the opinions of probable costs for each of the configurations of welded shields.

Section 6 outlines the mechanical design for a shield fastened with powder-driven pins, with the cost estimate given in Section 7.

Section 8 discusses requirements for shield quality control, effectiveness tests, and maintenance costs during the lifetime of the shield.

Conclusions and recommendations are given in Section 9, and References in Section 10.

Appendix A lists some factors affecting the cost estimates for the all-welded shield designs, and Appendix B presents detailed listings of construction materials and labor for all shield configurations studied.

SECTION 2

BASELINE DESIGN OF C³ FACILITY

2.1 FACILITY REQUIREMENTS



In order to obtain representative as well as comparative cost estimates for the various C³ facility shield designs, the following parameters and characteristics were selected for an assumed prototype C³ facility:

Building Size:	60 feet wide by 200 feet long by 20 feet high
General Construction:	One story, above ground, windowless, reinforced concrete
Personnel Occupancy:	60 to 80 men and 15 to 20 women, 24 hours/day, continuous use
Electronic Equipment:	3 transmitters, each 10 kW output power 20 to 30 receivers 8 to 10 TTY computer and peripherals standard office equipment
Geographic Location:	Midwestern U.S.
Shield Penetrants:	commercial power, 3 ϕ , 440 v Rms, 4-inch conduit water and sewage pipes telephone cable, 100 pairs coaxial cables: ten one inch conduits, five two-inch conduits waveguides: two 1 1/2 x 3 inches
Shield Type:	steel envelope, continuous entry vault; 1/4 inch steel entry plate
Access Doors:	Personnel: main entrance/exit; emergency exit Cargo: sliding door
Shield Lifetime:	20 years minimum

2.2 BASIC ARCHITECTURAL AND STRUCTURAL DESIGN

For purposes of evolving shield designs and shield cost estimates, the building floor plan shown in Figure 1 was used. Approximately 70 percent of the floor area is devoted to four main rooms for receivers, transmitters, operations, and computer facilities. The remainder of the building is allotted to an entry vault, a receiving and storage area, washrooms, janitor closet, and corridors. A separate, unshielded, Engine Generating Building is assumed.

The entry vault serves to house protective devices such as surge arresters, filters and circuit breakers to reduce the EMP energy which the penetrants would otherwise cause to couple into communications circuits and electrical power lines. Two separate sections






FIGURE I. ARCHITECTURAL/STRUCTURAL FLOOR PLAN



2

of the vault are provided: one for the entering electrical power lines, and one for the communications lines. The costs for the protective devices normally within the entry vault are not included in this cost study.

All doors for personnel entry and exit in the C³ facility are hinged. The main entrance/exit has a standard outside all-weather door plus two shielded doors in a shielded vestibule. The shielded doors are assumed to be interlocking so that only one can be open at any given time. The emergency exit has one shielded door, normally closed, and an all-weather exterior door.

The cargo/storage area has a standard exterior roll-up door on the cargo dock. The storage room itself has two shielded sliding doors, one on each side of the (shielded) storage room. Again, the doors are interlocked so that only one can be open at any one time.

The building is assumed to be poured-in-place reinforced concrete. The roof slab is 20 feet above a 6 inch floor slab on grade. Roof support is provided by seven columns 20 by 20 inches, 25 feet on center, along the building centerline, and by a 6 inch perimeter wall.





The building is not designed to be blast-proof. It was found that no additional structure is needed to carry the five pound per square foot loads imposed by the steel shielding. The structural design, therefore, is in no way different from that of a conventional building, and no additional costs are incurred. The building is designed in conformance with the Uniform Building Code, 1978 edition, under the category "Office Buildings".

The Computer Room is to have a raised floor, finished, as are floors in all other areas, in vinyl asbestos tile. Ceilings are to be acoustic tile with 2 x 4 foot fluorescent fixtures located four feet on center. Walls are assumed to be covered with painted gypsum wall board. When interior shielding is used, special techniques are required to apply to or suspend the ceiling from the ceiling shield.


2.3. UTILITIES DESCRIPTIONS

2.3.1 Heating, Ventilating, and Air Conditioning

Self-contained air-conditioning units, with an automatic temperature and humidity control panel, are utilized in the Transmitter and Computer Rooms. These units are to have individual, remote, dry cooler condensers on the roof, with interconnecting steel water piping penetrating the shield. Each of these rooms is to be provided with two units, each sized to handle two-thirds of the heat load for the room. Ventilation required for these rooms is to be provided by a central unit (see Figure 2).



SECTION "A"



**FIGURE 2. HVAC PLAN
WALL PENETRATIONS**



2

A separate, variable-air-volume, unit is to be located in the Mechanical Equipment Room to serve the Operations Office, Receiver Room, Corridor, and Storage Room. A matching air-cooled condensing unit mounted on the roof is also to be provided. An exhaust-return fan is to be provided to utilize outdoor air for cooling. Shield penetrations for this system are to be as follows: 5 feet by 2 feet for outdoor air intake; a 2 feet 6 inch exhaust return fan discharge; and steel piping from the condensing unit. Duct penetrations are to terminate at RF honeycomb shielded air vents. Air supply systems for this unit are to be arranged so that air can be temporarily diverted to either the Transmitter Room or Computer Room in case one of the room air-conditioning units is out of operation.

Exhaust fans for Toilet Rooms and the Mechanical Equipment Room are to be provided. Fans are to be located indoors, and the exhaust duct is to discharge outdoors through an RF honeycomb shielded air vent.

The heating system is assumed to be electrical and the main entrance is to be provided with an individual electric cabinet unit heater. Electrical unit heaters are to be provided in the mechanical, equipment room and in the emergency generator room.



Ductwork and points of shield penetrations are identified in Figure 3.


2.3.2 Electrical

The plan in Figure 4 identifies all points at which electrical conduit penetrates the shield to serve the power, lighting, communications, and security systems. Each of these points is to be protected as detailed later in the discussion of penetrations. The size, location, and number of penetrations are based on maximum equipment power requirements as assumed here. They are as follows: Transmitter Room, 80 K W at 208V/120 volts; Receiver Room, 32 K W at 208V/120 volts; Computer Room, 100 K W at 208V/120 volts; and Operations Office, 10 K W at 208V/120 volts.

Lighting levels are based on Illuminating Engineering Society recommendations, and the system is designed to operate at 277 volts. The intensities are as follows: equipment areas 70-100 foot-candles (F C); corridor, 20-30 F C;


Diversity and demand figures are based on 24 hour-per-day, 7 day-a-week operation, with simultaneous equipment operation. The estimated total loads are as follows: equipment, 222 K W; lighting, 45 K W; and H V A C, 133 K W; total load is therefore 400 K W. Standby power generation is required to provide 100% emergency power for a 30-day period. On the basis of a load of 400 K W, a 440 KW, 480V diesel engine-generator, rated for continuous operation, is required.





**FIGURE 3. HVAC PLAN
ROOF PENETRATIONS**





- A. 2-3" C POWER
2-1" C CONTROL/ALARM
1-2" C SITE LIGHTING
1-1 1/2" C SECURITY
1-2" C GENERATOR BUILDING POWER

- B. 3-2 1/2" C TELEPHONE
10-1" C RECEIVER
5-2" C TRANSMITTER
2-3" x 1 1/2" WAVEGUIDE

- C. 1-3/4" C LIGHT & RECEPTACLE

- D. 2-4" C POWER
3-2" C POWER
1-1 1/2" C SECURITY


- E. 1-3/4" C LIGHT & RECEPTACLE
1-3/4" C SECURITY

- F. 1-3/4" C LIGHT & RECEPTACLE
1-1 1/2" C SECURITY
1-1" C ELECTRIC HEATER

- G. UP TO
1-1" C
1-3/4"

- H. SHIELD

- J. POWER
8-40
8-25
4-10



**FIGURE 4. ELECTRICAL PLAN
WALL/ROOF PENETRATIONS**

UP TO ROOF
1 - 1" C POWER
1 - 3/4" C CONTROL

SHIELDED ENTRY BOX

POWER CABLE FILTERS
6 @ 400A
8 @ 200A
4 @ 100A

HARDEN THE FOLLOWING ITEMS LOCATED IN REMOTE GENERATOR BUILDING
1. CONTROLS
2. BATTERY CHARGER



2

The following conduit requirements are assumed: ten 1 inch conduits for the Receiver Room; five 2 inch conduits for the Transmitter Room; and two 3 by 1 1/2 inch wave guides. Telephone requirements are taken at three times the commercial need for similar occupancy, or 2 1/2 inch conduit. In addition, a 1 1/2 inch conduit is provided for security monitoring.

Because of engine heat rejection, combustion air requirements, and noise problems, it was considered desirable to locate the engine-generator in a separate building. Most of the control equipment is to be located in the shielded area of the C³ building. However, such items as the engine alternator and battery charger are to be located in the Generator Building. These items are to be individually EMP-hardened. The Generator Building itself is not shielded.



2.3.3 Plumbing/Fire Protection

The cold water supply is to be metered in the Emergency Generator Building before it is extended into the C³ facility. A separate cold water source may be provided either by a storage tank or by a deep-well pump. An electrical hot water heater is to be provided in the Mechanical Equipment Room to serve all lavatories in the Toilet Rooms.

Roof drainage is to be collected through scuppers and outdoor metal downspouts. All plumbing fixtures with complete piping connections are to be provided, and shield penetrations are shown on the plan in Figure 5.


All piping below the floor slab is to be non-metallic. Floor penetrations of plumbing pipes are to be as discussed in Section 3, and are located on the plan in Figure 5. A second source of domestic water is to be carried to the building from municipal mains. It is assumed that no water-cooled computer equipment is to be provided for.

While it is certain that the C³ building would have a fire protection system, these requirements have been omitted here since they would be expected to affect all shield designs approximately equally.



NOTES:

- I. UNDERGROUND
PIPES TO BE PLA



**FIGURE 5. PLUMBING PLAN
FLOOR PENETRATIONS**



GROUND SANITARY & COLD WATER
BE PLASTIC

2

SECTION 3

ELECTRICAL DESIGN FOR SHIELDS

3.1 INTRODUCTION

This section of the report first discusses the shielding requirements in terms of a threat level of EMP radiation incident upon an infinite flat shield. Then the current concentrations along edges of a realistic shield and currents injected onto the shield from penetrants are considered.

Next, the design approach is discussed. Initially, linear behavior of the shield is assumed, and the transmission line approach is used. A rationale is presented for requiring the specified shielding to be obtained from absorption loss only, without relying on reflection loss. This requirement, in turn, indicates the use of a ferromagnetic material, if shield thickness is not to become unreasonable.

Realistic threat levels of EMP radiation can cause at least partial saturation of a steel shield. A simplified discussion of the possible effect of saturation on shielding effectiveness is presented, and a family of curves is plotted showing the shield thickness required for a given degree of shielding for incident pulses of various durations and amplitudes.

Sketches are later presented showing the shield configurations for each of the four facility construction options for a welded shield. A fifth construction option, using powder-driven pins for fastening the shield, uses the same shield configuration as one of the welded designs.

3.2 SHIELDING REQUIREMENTS

3.2.1 Plane Wave Incident on Infinite Flat Sheet

As the simplest example of an EMP threat, consider a plane wave with an electric field strength of 50 kV/m incident on an infinite flat shield. The magnetic field intensity of the incident wave is then:

$$H_i = \frac{E}{\eta} = \frac{50 \text{ kV/m}}{377 \text{ ohms}} = 133 \text{ A/m} \quad (1)$$

where η is the intrinsic impedance of free space.

When a plane electromagnetic wave is normally incident on a good conductor, the reflected wave is virtually the same amplitude as the incident wave. At the reflecting surface, the incident and reflected magnetic fields are in phase. Therefore, the total magnetic field, H_s , at the surface is twice the incident field:

$$H_s = 2H_i = 266 \text{ A/m} = 3.3 \text{ Oersted} \quad (2)$$

3.2.2 Corner Effects

For a box-like shielded enclosure, the shielding effectiveness is commonly said to be "degraded" at the edges and corners of the enclosure. This so-called degradation is not due to any change in the intrinsic behavior of the shield material (assuming a linear, non-saturating shield), but rather due to the particular distribution of currents on the outer surface of the enclosure. The higher current concentrations along the edges produce higher magnetic fields there, and these, in turn, cause higher magnetic fields on the inside of the enclosure, in the region of edges and corners.

Figure 6 shows this effect. For example, within a distance $0.1a$ from a corner -- where $2a$ is the wall dimension -- the field is approximately 30 dB greater than if the shield were a planar sheet (of the same material and thickness). Therefore, for a 60 foot wall dimension, the internal field will be 20 dB higher within 3 feet of the corner.

It may be desirable to impose the restriction that sensitive, susceptible equipment be excluded from the small regions within some short distance from the corners. Then, under the conditions for which the given curve applies, maintaining a 3 foot corner clearance for a 60 foot wall would indicate that the field will be no greater than 20 dB above the planar condition.

Therefore, if it is desired to achieve a shielding level of 100 dB (except within three feet of a corner, where the fields would be stronger), the shield material and thickness should be selected such that an infinite planar sheet of that material and thickness would provide 120 dB shielding.

3.2.3 Currents from Penetrants

A metallic conductor, e.g., a pipe or a cable sheath, entering a shielded facility will be circumferentially welded to the shield at the entry point. Current flowing on the conductor is then discharged onto the outer surface of the shield. It is of interest to estimate the magnitude of the resulting current density on the shield.

If the current of magnitude I flows radially from the penetration point, the current density J at any radius r is:

$$J = \frac{I}{2\pi r} \quad (3)$$

Assuming a current of 1500 A, and an observation point on the shield at a distance $r = 1$ meter away from the penetrant, $J = 250 \text{ A/m}$. This is approximately the same as the level calculated in Section 3.2.1 for an incident plane wave.




Figure 6 SHIELDING DEGRADATION NEAR CORNERS
IN A SHIELDED SPACE

3.2.4 Numerical Examples

It has previously been reported¹ that a useful way to specify an upper limit on electromagnetic fields within a C³ facility is to set a limit on the maximum time rate of change of magnetic field, dH/dt or \dot{H} . Such a specification can limit to safe values the maximum voltage induced in a typical electronic circuit. The maximum limit inside the C³ facility was suggested as:

$$\dot{H}_{\max} = 3(10)^5 \text{ A/m/second.} \quad (4)$$

If the field varies sinusoidally, i.e.,

$$H = H_i \sin \omega t, \quad (5)$$

$$\text{then} \quad \dot{H} = \omega H_i \cos \omega t, \quad (6)$$

$$\text{and} \quad \dot{H}_{\max} = \omega H_i = 2 \pi f H_i \quad (7)$$

$$\text{Letting} \quad \dot{H}_{\max} = 3(10)^5 \text{ A/m/second and } f = 10 \text{ kHz}$$

$$H_i \approx 2.5 \text{ A/m.} \quad (8)$$

If the shield provides 100 dB shielding, the maximum permissible current density (at 10 kHz) at the outer surface of the shield is $10^5 H_i$, or 250,000 A/m. If the shield provides 120 dB shielding, the permissible external current density (at 10 kHz) is $2.5 (10)^6$ A/m.

From an alternative viewpoint, the required level of shielding can be derived by considering the transient phenomena of a 50 kV/m plane wave pulse of 10 nanosecond rise-time incident on the shield. In Section 3.2.1 the magnetic field at the outer surface of the shield was found to be 266 A/m. Then, for a 10 nanosecond rise time,

$$\dot{H}_{\text{outside}} = \frac{266 \text{ A/m}}{10^{-8} \text{ second}} \approx 3 (10)^{10} \text{ A/m/second} \quad (9)$$

Using the previously suggested limit of $\dot{H}_{\max} = 3(10)^5$ A/m/second inside the enclosure, the required shielding level is $3 (10)^{10} / 3 (10)^5 = 10^5$, or 100 dB.

3.3 DESIGN APPROACH

3.3.1 Design Assuming Linear Behavior of Shield

For the purposes of this study, the achievable shielding effectiveness for a given shield material and thickness was estimated on the basis of the transmission line equations. While these equations are strictly valid only for a plane wave front incident upon an infinite planar sheet, or for certain other canonical examples, they were used as an approximation. Under these conditions the shielding effectiveness is given by:

$$S = R + A + B \quad (10)$$

where

S = Shielding effectiveness (dB)

R = Reflection loss (dB)

A = Absorption or penetration loss (dB)

B = Rereflection correction term (dB). Usually negligible; it must be included only if A is less than 15 dB.

The Reflection Loss term can, itself, provide a very significant rejection of incident radiated energy because of the large mismatch between the impedance of the incident wave and the intrinsic impedance of the metallic shield. However, it may not always be possible to rely on reflection loss. A C^3 facility will ordinarily have attached power and telephone cables and possibly metallic pipelines. These long conductors can collect large EMP currents which, can then be injected directly onto the exterior surface of the shield. These large surface currents produce strong magnetic fields directly on the near surface of the shield. In this case, there is no reflection loss, and only the absorption loss can be relied on. Thus, the shield materials and thicknesses considered were based on absorption only, resulting in a relatively conservative shield design.

Shielding is required over the frequency range 10 kHz to 100 MHz. Through most of this range the shielded structure is small compared with a wavelength, and therefore does not even approximate the infinite planar surface assumed in applying the transmission line equations. The surface currents on the shield will therefore, not be uniform, but will tend to concentrate near the corners of the structure as discussed in Section 3.2.2. As explained there, in order to achieve 100 dB shielding effectiveness within three feet of a corner of the building, the shield material and thickness should be selected to provide 120 dB shielding as calculated for a planar shield.

For a shielding material with constant electrical parameters of conductivity and permeability, the absorption loss for a plane wave normally incident on a flat sheet of infinite extent is given by:

$$A = 3.34 (10)^{-3} t \sqrt{\sigma_r \mu_r f} \quad (11)$$

where t = sheet thickness in mils (thousandths of an inch)

σ_r = conductivity, relative to copper

μ_r = permeability, relative to copper

f = frequency, in Hz.

As seen from the equation for A, the absorption loss increases rapidly with frequency, assuming constant values of σ_r and μ_r . Although some investigators have reported μ_r of ferrous materials to decrease with frequency, the effect is probably not as significant² as once believed. In any case, the product $\mu_r f$ increases with frequency, and therefore, A increases with frequency for a given value of t. Thus for a given required value of absorption loss A, the material type and thickness t should be selected to provide the required value of A at the lowest frequency of interest.

In this case, where the specified level of shielding must be provided down to 10 kHz, the equation for A becomes:

$$A = 0.334 t \sqrt{\sigma_r \mu_r} \quad (12)$$

This equation is graphed in Figure 7 for three materials with the following values² assumed for σ_r and μ_r :

	σ_r	μ_r
Copper	1	1
Stainless Steel	0.028	227
Hot Rolled Steel	0.16	160

It is seen from Figure 7 that for a given sheet thickness, the hot rolled (low carbon) steel provides substantially more absorption loss than either the stainless steel or copper. Or, conversely, hot rolled steel can provide a specified absorption loss with the thinnest sheet, whereas copper requires the thickest.

To achieve an absorption loss of 120 dB at 10 kHz would require a copper sheet approximately 360 mils (9 mm) thick. Such a shield would be very heavy and very expensive. For stainless steel, a thickness of only 142 mils (3.6 mm) would be required, but would also be expensive. For hot rolled steel, a sheet thickness of only 71 mils (1.8 mm) could provide 120 dB absorption.

However, as will be explained later in the report, due to a difference in the costs of field welding steel sheets, a shield constructed of 14 gauge* (75 mil) steel sheets would be more expensive than one using heavier gauge sheets, e.g., 11 ga. Therefore, use of 11 ga (120 mil or 3 mm) hot rolled, low carbon steel, is recommended for the welded shields. From Figure 7 it is seen that 120 mil hot rolled steel sheets could provide an estimated 200 dB planar absorption loss if the electrical parameters of the steel remained constant and the steel did not saturate. However, saturation of ferrous materials can occur for high incident levels of magnetic fields, affecting shield performance considerably. The effects of saturation are discussed in Section 3.3.2 below.

*Thicknesses of standard gauge metal sheets are listed in Table 1.




Figure 7. PLANAR ABSORPTION LOSS AT $f=10\text{KHz}$

Table 1
Standard Thickness of Metal Sheets

Gauge	Steel		Non-Ferrous	
	Inches ¹	MM	Inches ²	MM
1				
2				
3	0.2391	6.1	0.2294	5.8
4	0.2242	5.7	0.2043	5.2
5	0.2092	5.3	0.1819	4.6
6	0.1943	4.9	0.1620	4.1
7	0.1793	4.6	0.1443	3.7
8	0.1644	4.2	0.1285	3.3
9	0.1495	3.8	0.1144	2.9
10	0.1345	3.4	0.1019	2.6
11	0.1196	3.0	0.0907	2.3
12	0.1046	2.7	0.0808	2.1
13	0.0897	2.3	0.0720	1.8
14	0.0747	1.9	0.0641	1.6
15	0.0673	1.7	0.0571	1.45
16	0.0598	1.5	0.0508	1.3
17	0.0538	1.36	0.0453	1.15
18	0.0478	1.2	0.0403	1.02
19	0.0418	1.1	0.0359	0.91
20	0.0359	0.91	0.0320	0.81
21	0.0329	0.84	0.0285	0.72
22	0.0299	0.76	0.0255	0.64

Notes: 1) Manufacturers Standard
2) Brown & Sharp

Source: Central Steel & Wire Company
Chicago, Illinois

As discussed in Section 6, thinner material, e.g., 14 ga (75 mil) or 18 ga (48 mil) might be used if the shield were fastened using powder-driven pins rather than welding. It is seen from Figure 7 that sheets of these thicknesses could provide planar absorption losses of 120 dB and 80 dB, respectively, at 10 kHz.

3.3.2 Effect of Magnetic Saturation on Shield Design

The calculations of shielding effectiveness (absorption loss) as determined in Section 3.3.1 were based on linear behavior of the shield material. While a non-ferromagnetic material such as copper can be assumed to be linear for all electromagnetic field levels of interest, steel will be nonlinear and could become magnetically saturated at some threat levels. This section presents a simplified discussion of the possible effect of saturation on the shielding effectiveness of a steel shield. The depth of saturation of the shield is dependent on the time integral of the density of surface current flowing on the shield. A family of curves is plotted showing the shield thickness required for a given degree of shielding (120 dB shielding at 10 kHz) for incident pulses of various durations and amplitudes.

The calculations presented here initially follow the approximate approach by Ferber and Young³⁻⁵ in which a limiting nonlinear theory predicts a lower bound on shielding effectiveness. The procedure adopted here is as follows. As shown in Figure 8, the actual magnetization curve of the ferromagnetic material is approximated by a limiting curve characterized by two parameters:

B_{SAT} , the saturation magnetization (Wb/m^2)

H_C , the coercive force of the material.

If a high intensity magnetic field H_S (where $H_S > H_C$) is applied to the surface of the steel sheet, the region exposed to the strong field saturates, and the region or depth of saturation propagates into the material as long as the magnetic field incident wave exceeds the saturation level. The field at the inner edge of the saturated region is of magnitude H_C , the coercive force of the material. Thus, even with the saturation phenomena, the material still may provide a significant amount of shielding.

Figure 9 shows a cross-section of the steel plate (of infinite extent) with an incident magnetic field, H_S , strong enough to saturate the material, applied to one surface. This field is considered to be due to a surface current flowing on the sheet. The current is pulsed, with a duration T . During the time T the saturated region propagates into the sheet a depth of δ^{SAT} , and the magnetic field intensity at the inner edge of the saturated region is H_C .




Figure 8. APPROXIMATION OF NONLINEAR MAGNETIZATION CURVE




Figure 9. MAGNETIC FIELD IN STEEL PLATE

After time T the surface current, and hence the applied field, are assumed to drop to zero. The inward propagation of the saturated region then ceases, and the field within the material then decays. The maximum depth of saturation δ^{SAT} depends on the magnitude and duration of the applied surface current which causes field H_s .

The remaining thickness of the steel sheet, $n \delta^{SKIN}$, is unsaturated and provides absorptive shielding at the rate of 8.68 dB for every skin depth of material in the unsaturated region. Thus, an unsaturated thickness of $n \delta^{SKIN}$ provides $n \cdot 8.68$ dB of additional shielding besides the shielding due to the saturation effect in the region of thickness δ^{SAT} .

The nature of the analysis here is to determine the minimum thickness, d , of the steel plate which will provide at least the required amount of shielding, designated here as SE (Shielding Effectiveness, in dB). In turn, the required thickness depends on the required number of skin depths and the magnitude of the skin depth, δ^{SKIN} . Since the magnitude of skin depth varies inversely with frequency, the procedure has here been adopted to determine the minimum required thickness of region $n \delta^{SKIN}$ based on the minimum frequency at which the required shielding effectiveness is specified, i.e., 10 kHz. Thus the calculation is made on a worst-case basis and will be conservative for other frequencies.

The shielding effectiveness is defined as:

$$SE = 20 \log_{10} \frac{H_s}{H_t} \quad (13)$$

where H_t is the magnitude of the field on the far side (inner surface) of the shield.

The exponential attenuation of n skin depths in the unsaturated region provides the relationship

$$H_t = \frac{H_c}{e^n} = \frac{H_c}{\frac{d - \delta^{SAT}}{\delta^{SKIN}}} \quad (14)$$

Therefore:

$$SE = 20 \log_{10} \frac{H_s}{\frac{H_c}{e \frac{d - \delta^{SAT}}{\delta^{SKIN}}}} \quad (15)$$

$$= 20 \log_{10} \left[\frac{H_s}{H_c} e^{\frac{d - \delta^{SAT}}{\delta^{SKIN}}} \right] \quad (16)$$

$$= 20 \log_{10} \frac{H_s}{H_c} + 20 \log_{10} e^{\frac{d - \delta^{SAT}}{\delta^{SKIN}}} \quad (17)$$

$$= 20 \log_{10} \frac{H_s}{H_c} + 20 \left(\frac{d - \delta^{SAT}}{\delta^{SKIN}} \right) \log_{10} e \quad (18)$$

$$= 20 \log_{10} \frac{H_s}{H_c} + 8.68 \left(\frac{d - \delta^{SAT}}{\delta^{SKIN}} \right) \quad (19)$$

Next, δ^{SAT} must be determined. An expression for δ^{SAT} has been previously derived⁴ for current flowing along the outer surface of a cylindrical tube:

$$\delta^{SAT} = \sqrt{\frac{\int_0^T i(t) dt}{\pi r_o \sigma B_{SAT}}} \quad (20)$$

where $i(t)$ = current flowing on cylindrical tube

r_o = outer radius of tube

σ = conductivity of conductor

B_{SAT} = saturated flux density

Two approximations will be made for applying this type of relationship to the present problem. First, it will be assumed that the current waveform is a rectangular pulse of amplitude I and duration T . Thus, the time integral of the current can be replaced by the product $I \cdot T$. Thus:

$$\delta^{SAT} = \sqrt{\frac{I \cdot T}{\pi r_o \sigma B_{SAT}}} \quad (21)$$

The second approximation will apply this type of relationship to a current of uniform density flowing on one surface of a flat sheet rather than on one surface of a cylindrical tube. The above equation can be rewritten:

$$\delta^{SAT} = \sqrt{\frac{I}{2\pi r_o} \cdot \frac{2T}{\sigma B_{SAT}}} \quad (22)$$

The term $I/2\pi r_0$ is the surface current density in Amperes/meter flowing on the tube. Denoting this surface current density by J_s , the equation becomes:

$$\delta^{SAT} = \sqrt{\frac{2 J_s T}{\sigma B_{SAT}}} \quad (23)$$

This expression will be assumed to apply to a current of density J_s flowing on one surface of a large flat sheet of ferromagnetic material.

The equation for shielding effectiveness then becomes:

$$SE = 20 \log_{10} \frac{H_s}{H_c} + 8.68 \left[\frac{d - \sqrt{\frac{2 J_s T}{\sigma B_{SAT}}}}{\delta^{SKIN}} \right] \quad (24)$$

Setting the surface magnetic field intensity H_s equal to the surface current density J_s , and rearranging to solve for d :

$$d = \frac{\delta^{SKIN}}{8.68} \left[SE - 20 \log_{10} \frac{J_s}{H_c} \right] + \sqrt{\frac{2 J_s T}{\sigma B_{SAT}}} \quad J_s \geq H_c \quad (25)$$

This equation applies for $J_s \geq H_c$, i.e., for the case of at least partial saturation of the shield. If $J_s < H_c$, no saturation occurs, and the required relationship becomes:

$$d = \frac{\delta^{SKIN}}{8.68} SE \quad J_s < H_c \quad (26)$$

The following parameters will be used as representative for hot-rolled, low-carbon steel:

$$\sigma_{r_{cu}} = 0.16; \sigma = 0.93 (10)^7 \text{ mhos/m}$$

$$\mu_{r_{cu}} = 160$$

$$H_c = 2 \text{ Oe} = 160 \text{ A/m}$$

$$B_{SAT} = 1.5 \text{ wb/m}^2$$

$$\delta^{SKIN} = 1.31 (10)^{-4} \text{ m (0.13 mm; 0.0051 inch)}$$

(Applies for 10 kHz)

$$SE = 120 \text{ dB}$$

Inserting these values in the equation for d:

$$d = 10^{-3} (2.47 - 0.30 \log_{10} J_s + 0.38 \sqrt{J_s T}) \text{ meter.} \quad (27)$$

Equation (27) is plotted in Figure 10 for values of $J_s \geq H_c$ (160 A/m). Also shown for $J_s < H_c$ is the required thickness (71 mils) for conditions where shield behavior is linear. It should be noted that the shielding effectiveness calculated in the linear region was for a single frequency (10 KHz) which is the worst-case. These curves are not intended to provide data to calculate the actual shielding effectiveness over the entire pulse spectrum.

Figure 10 shows that for a pulse duration of 10 microseconds, for example, a steel shield 120 mils thick (11 gauge) can provide 120 dB shielding for current surface densities up to approximately $4 (10)^6$ A/m. This density is approximately four orders of magnitude above the current density which would result from a 50 kV/m plane wave incident on an infinite flat sheet. For a shield of realistic shape, e.g., a rectangular parallelepiped, the current concentration near the edges and corners, might be estimated to be approximately three orders of magnitude above the density for an infinite flat sheet. Thus, it would appear that even with partial saturation, an 11 gauge steel shield can provide adequate shielding (e.g., 120 dB) under these conditions. Also, a shield 71 mils thick (14 ga) can provide 120 dB shielding at 10 kHz in the absence of any saturation.

3.4 SPECIFIC SHIELD CONFIGURATIONS

Figures 18, 22, 26, and 30, to be discussed later, show the shield configurations for each of four construction options:

- Condition I - New Construction, External Shield
- Condition II - New Construction, Internal Shield
- Condition III - Retrofit Construction, Internal Shield,
Interior Walls Replaced
- Condition IV - Retrofit Construction, Internal Shield,
Interior Walls Retained

The shield configuration for Condition V, New Construction, Internal Shield is the same as that for Condition II. For Condition V, however, the shield is fastened by powder-driven pins as will be described in Section 6.

In addition to an envelope shield enclosing the operational areas, entry vaults are provided for both the communications and the electrical power systems. If it were desired to consider a facility with a lower level of shielding, e.g., 30 dB, the entry vaults could be eliminated. In that case the entering communications and power lines would be routed through steel entry boxes.





Figure 10. MINIMUM THICKNESS OF STEEL



Current Density J_s In A/m

STEEL SHIELD FOR 120 DB ABSORPTION LOSS

The entry plate is 1/4 inch steel plate. Penetrants entering the facility through the entry plate are circumferentially welded to the plate.

It should be noted that for Condition I, New Construction, External Shield, a significant amount of internal shielding is required, including internal ceiling shields on the personnel entry vestibule and the storage room, in addition to the entry vaults.

The next section of the report describes mechanical details of the welded shield construction for each of the four conditions. Section 6 describes the design for a shield fastened by powder-driven pins.

SECTION 4

MECHANICAL DESIGN FOR WELDED SHIELDS

4.1 GENERAL


4.1.1 Envelope Shield

At the outset of this study, it was considered that three different levels of shielding 30, 60, and 100 decibels (dB) -- would be analyzed for each of the four welded shield designs (Conditions I, II, III, and IV). This would have indicated the use of three gauges of steel plate -- 22, 18, and 14 gauge, respectively, for the major portion of the shield.

As the study progressed, it was learned that 18 and 22 gauge steel cannot be field-welded, although 18 gauge can be factory-welded under controlled conditions. Consequently, no further consideration was given to these lighter gauge plates.

Fourteen gauge plate can, under carefully controlled conditions and with special equipment, be field-welded. However, it is difficult to ensure continuity of the weld (and, therefore, the shield), and some wastage of material burned through during welding is to be anticipated. It is estimated that approximately \$20,000 in materials cost can be saved by using 14-gauge as opposed to 11-gauge steel for Condition I. However, it is also estimated that labor costs would rise by approximately 30% (90,000 dollars). It appears that, in the long run, \$70,000 can be saved by using the heavier material. This saving, about ten percent, is found to be typical in all four conditions.

The cost-effectiveness of using only 11 gauge steel has the obvious benefit of providing 100 dB shielding in all cases being studied. The only possible saving for any of the three shielding levels is that an entry vault would not be required for the 30 dB shielding level. Instead, incoming lines penetrating the entry plate could pass through shielded entry boxes, welded to the entry plate for interior shields as shown in Figure 11. These shielded entry boxes would have the surge arresters, etc. In view of the relatively small cost saving associated with this design change for 30 dB shielding, it has not been included, and only the 100 dB shielding level has been considered for the welded shield designs.



**FIGURE II. TYPICAL SHIELDED ENTRY BOX
(FOR 30db SHIELDING)**

The entry plate in all cases is a 1/4 inch thick steel plate extending the width and height of one end of the building through which all penetrants are assumed to enter.

The typical 11 gauge plate to be used is standardized at 5 by 10 feet in size. When applied to walls, the long dimension is always vertical, thereby maximizing vertical joints, but reducing horizontal joints to one (see Figure 12). This has two advantages: it is easier to full-fillet weld vertically than it is horizontally, and it eliminates the need for an expansion joint, since thermal movement is distributed over 40 panels and joints in the length of the building. A maximum width of 3/8 inch is to be allowed between panels to compensate for allowable dimensional discrepancies in building construction. This corresponds to the maximum practical width for the full-fillet weld used to fill the gap between panels.

Panels are to be fastened to walls or slabs as follows: a 1/4 inch by 4 inch steel bar is attached to the wall with 3/8 inch by 4 inch steel studs driven through, or cast into, the concrete 10 feet apart in the long dimension of the panel, and approximately 1.7 feet apart in the short dimension. In this manner, there is a bar around all panel edges, and at third points parallel to its long dimension (see Figure 13).

Likewise, the panel has rows of 1/2 inch diameter holes pre-punched on 2-foot centers* on lines at third points parallel to the long dimension. When the panel is positioned on the wall or slab, the holes (which align with the bar behind) are filled with plug welds, this securing the panel to the bar and wall. Plug welds on floors, and wall shielding in Condition 1, are to be ground smooth. Joints between panels (which also occur along bars) are full-fillet welded, thereby providing continuity of shielding between panels and completing the installation of that panel.

This procedure is used in all instances, except when the wall material is concrete block, not poured-in-place concrete. In these cases, the bar and wall are both pre-drilled, and an anchor bolt replaces the steel stud as the means of initial attachment. Otherwise, the procedure described above remains identical.

The steel plate is to be hot-rolled low carbon steel conforming to ASTM A569-72, or similar specifications. Metal Inert Gas (MIG) continuous fillet welds are to be applied in alternate strips of weld no more than six inches long. Exposed exterior panels are to be protected by a chromate primer and paint.

*One foot for exterior wall application.





Figure 12. ARRANGEMENT OF WELDED STEEL PLATES ON WALLS



**FIGURE 13. TYPICAL SHIELDING PLAN
FOR FLOOR AND CEILING**



4.1.2 Penetrations

Each time the shield is interrupted by an opening or penetration, special measures must be taken to re-establish the continuity of the shield as well as possible. These penetrations are of three general types: doors (the C^3 structure has no windows), ducts (air intake and discharge), and piping (electrical conduit, water supply, sanitary drainage, etc.). In order to minimize the number of penetrations, roof drainage is limited to the exterior of the building by the use of gutters and downspouts.

As mentioned earlier, penetration by doors is accomplished using shielded doors in conjunction with a shielded vestibule. The doors themselves are properly shielded and their edges are in close contact with the door frame. For hinged shielded doors, the door edge closes tightly against finger stock recessed in the door frame (Figure 14). Hinged shielded doors 3 feet by 7 feet are assumed.

For sliding doors, a design is available with pneumatic sealing and not requiring finger stock or RF gaskets. It is claimed to be reliable both mechanically and electrically for five years. Over a 20 year shield lifetime, several replacements would be required, as indicated in Section 8. Sliding shielded doors 8 feet by 8 feet are assumed for the cargo/storage area.

Ductwork to introduce fresh air and discharge stale air is protected with a RF honeycomb air vent utilizing the waveguide-beyond-cutoff principle (See Figure 15). For the largest intake duct, 5 feet by 2 feet, and a honeycomb cross-section of 2 inches by 2 inches, the honeycomb length must be at least 13 inches in order to provide 120 dB attenuation of the highest EMP frequencies of interest.

Piping penetrations are handled in either of two ways as shown in Figure 16. Continuous metal pipes are circumferentially welded to the entry plate as shown in Figure 16(a). Non-metallic pipes pass through the steel entry plate via a metal penetration pipe or "stuffing tube" which is circumferentially welded to the entry plate (Figure 16(b)). Here, again, the waveguide-beyond-cutoff principle is used; the section of metal penetration pipe must be at least 3 times its diameter. Similarly, Figure 17 shows a metallic pipe penetration and termination into a non-metallic pipe. Again, the length of the metal penetration pipe must be at least 3 times its diameter.

These three methods of maintaining continuity of shielding for penetrations of doors, ducts, and pipes are common to each of the specific shield configurations considered.








FIGURE 14. TYPICAL SHIELDED DOOR



**FIGURE 15. TYPICAL PENETRATION DETAILS
INTAKE/EXHAUST DUCT**



**FIGURE 16 . TYPICAL PENETRATION DETAILS
PIPE & CONDUIT**



**FIGURE 17. TYPICAL PENETRATION DETAILS
(FLOOR DRAIN)**



4.2 CONDITION I, NEW CONSTRUCTION, EXTERNAL SHIELD

In the first of the four Conditions it is assumed that the prototype C³ structure is to be of new construction and that the shielding will be applied to the exterior of the building as shown in Figure 18. In addition, internal shielding, including ceiling shielding, is required in the entry vault, storage room, and vestibule. These details are shown in the isometric sketch in Figure 19.


Generally, shielding and penetration details are as previously described in Section 4.1. However, certain details are unique to this Condition. It is assumed that, once the formwork for the footings and foundation wall is constructed and the concrete has been properly placed, a prefabricated steel cap plate is to be used to close the top of the form. This plate is to be 5 feet long, the width of the foundation wall, and is to be penetrated by steel reinforcing bars welded to it. These bars, which are to extend both above and below the plate, are to provide continuity of structural reinforcement between the foundation and upper walls. As will be shown, the plate will also provide continuity of shielding.

Once the foundation concrete has set and the forms have been stripped, the floor slab and walls can be poured. The prefabricated base plate is to be equipped with two elements in addition to the reinforcing bars. The first is a 1/4 by 4 inch steel bar cast into the edge of the floor slab. This is to provide a continuous perimeter "seat" onto which the floor shielding is to be fillet-welded to the cap plate. The second is a 2 by 2 inch continuous-steel angle pre-welded to the topside of the "exterior" edge of the base plate. It is to this angle that the bottom edge of each exterior wall plate is to be fillet-welded. In this manner, continuity of shielding between interior floor and exterior wall shielding is maintained as it passes through the foundation wall (Figure 20).

Although the floor slab is separated from the foundation by a construction joint, slab and foundation steel reinforcing is continuous to prevent separation of floor slab and walls during normal building settling, and consequent cracking of the shield. Also, although not shown in Figure 20, steel reinforcing is used at the wall-roof joint and other joints to prevent separation. Similarly, in subsequent wall-detail sketches, steel reinforcement is not shown but should be understood to be included at all construction joints to prevent separation and damage to the shield.



1



**FIGURE 18. CONDITION I
SHIELDING PLAN**







FIGURE 19. CONDITION I
ISOMETRIC



When the roof slab is poured, a continuous 4 x 4 x 1/8 inch steel angle is to be cast into it along the perimeter. The upper edge of wall panels and the outside edge of roof panels are then to be continuously fillet-welded to this angle. A similar angle was cast into the vertical outside corner of walls, to which the vertical edges of the end walls panels are to be fillet-welded (Figure 21).


Exterior wall welds, whether continuous fillet (at joints between panels) or plug type, (along third points of the panel) are to be ground smooth. The wall is then to be protected with a chromate primer and paint. Floor plate welds are also to be ground smooth and covered with vinyl asbestos tile. Roof slab shielding is to be painted with a chromate primer prior to being covered with conventional built-up roofing. All other architectural details and finishes are as described in Section 4.1.

4.3 CONDITION II, NEW CONSTRUCTION, INTERNAL SHIELD

In the second of the four Conditions, it is assumed that the prototype C³ building is to be of new construction. In this case, however, the shielding is assumed to be applied to the interior surfaces of the structure as shown in Figures 22 and 23.



Generally, shielding and penetration details are as described in Section 4.1. However, certain details are unique to this Condition (See Figures 24 and 25). Continuity of floor, wall, and roof shielding is to be achieved by the use of 4 x 4 x 1/8 inch angles cast into the concrete at the intersections between the wall and the floor or roof slabs. The steel panels are then to be fillet-welded to the angles to provide a continuous shield. In this condition, beams and columns also need to be covered. Columns are encased in prefabricated steel "U" shaped sections of steel plate which are to be welded to steel bars cast into the column. Beams are to be similarly encased in prefabricated "U" shaped sections. These brake-formed sections also have an additional "ear" at the top of the "U" shape. This is done so as to make the interval between beams an even 10 feet -- the dimension of the standard steel panel. The beam enclosure plate itself utilizes a 6-foot wide panel, also an industry standard size.


All floor welds are to be ground smooth prior to installation of vinyl asbestos tile. Standard metal studs are to be tack-welded to vertical steel plate and shimmed as required by any irregularities of the wall surface. Gypsum wallboard is then to be applied in standard fashion, taped and painted.



**FIGURE 21. CONDITION I
HORIZONTAL WALL DETAIL**







**FIGURE 22. CONDITION II
SHIELDING PLAN**









FIGURE 23. CONDITION II
ISOMETRIC





**FIGURE 25. CONDITION II
HORIZONTAL WALL DETAIL**





The ceiling system and ductwork is to be suspended from steel rods welded to the underside of the roof slab shielding. The rods are placed on 2 foot centers and in rows 20 inches apart. This is done so that the rods are located along the same lines of support as is the plate, which is attached to the slab by means of 1/4 by 4 inch steel bar and cast-in-place steel stud. In this way, the weight of the ceiling, light fixtures, and ductwork is transmitted directly to the slab without penetrating the shield (see Figure 24). All other architectural details and finishes are as described in Section 4.1.

4.4 CONDITION III AND III A, RETROFIT CONSTRUCTION, INTERNAL SHIELD, INTERIOR WALLS REPLACED

In the third of the four Conditions, it is assumed that the prototype C³ structure is an existing building for which the shield is to be retrofitted. It is further assumed that the shield is to be applied to the interior surface of the building and that all existing interior partitions are to be removed before, and replaced after, the shielding is installed. Sub-Condition IIIa differs from Condition III only in that concrete block, rather than poured-in-place, walls are assumed. Figures 26 and 27 show the shield.

Generally, shielding and penetration details are as previously described in Section 4.1. Those details which pertain to this condition are similar to those described for Condition II in Section 4.3 except for two items. One difference is the additional work involved in the removal and replacement of all interior partitions - a procedure which in no way affects the design or details of the shield itself. It is assumed that little, if any pre-existing fixtures, ductwork, wiring etc. will be salvaged and be re-used.

The second difference between Condition III/IIIa and Condition II is the manner in which the 1/4 by 4 inch steel bar behind panel joints is secured to the wall. With new construction (Conditions I and II) the bar is to be prefabricated with 3/8 by 4 inch steel studs welded to it. The bar is then to be nailed to the formwork through pre-drilled holes and is to be subsequently cast into the concrete. In the retrofit situations (Condition III and IV), the bar is to be positioned against the wall, and the 4 inch steel stud shot through the bar into the poured-in-place concrete behind it as indicated in Figures 28 and 29. This procedure is not feasible when the existing wall is of concrete block construction (Conditions IIIa and IVa). In these instances, it is necessary to pre-drill both the bar and the concrete block wall, and secure the one to the other with toggle or expansion bolts. Once this work has been completed, installation of the shield can proceed.






FIGURE 26. **CONDITION III/IIIa
SHIELDING PLAN**



2




FIGURE 27. CONDITION III/IIIa
ISOMETRIC





FIGURE 28. CONDITION III/IIIa
 VERTICAL WALL DETAIL



**FIGURE 29. CONDITION III/IIIa
HORIZONTAL WALL DETAIL**



The interior finishes also remain the same and are installed in a manner similar to that described under Condition II. New partitions are assumed to be gypsum wallboard on steel studs. The studs and baseplate are to be tack-welded to wall and floor shielding, respectively.



4.5 CONDITIONS IV AND IVA, RETROFIT CONSTRUCTION, INTERNAL SHIELD, INTERIOR WALLS RETAINED


In the last of the four Conditions for the all-welded shield it is assumed that the prototype C³ structure is an existing building which is to be retrofitted, that the shield is to be applied to the interior surface of the building, and that all existing interior partitions are to remain in place. Sub-Condition IVa differs from Condition IV only in that it assumes concrete block rather than poured in place concrete exterior walls. Generally, shielding and penetration details are as previously described in Section 4.1. Many details which pertain to this condition are similar to those described for Conditions II and III. Again, it is assumed that little, if any, pre-existing fixtures, ductwork, wiring, etc., will be salvaged and re-used.

A major difference with Conditions IV/IVA compared with Condition II is the problem of providing a continuous floor shield and a continuous ceiling shield in the presence of floor-to-ceiling interior partitions which are to remain in place. A continuous shield can be constructed only by shielding both faces of all interior partitions, as shown in Figures 30 and 31. This understandably results in substantially increased amounts of material and labor. Beam enclosures must be fabricated in two "L" shaped sections rather than one "U" shaped section where beams are on partition lines, for instance. Details of horizontal and vertical walls are given in Figures 32 and 33.

The interior finishes are also to remain the same, and are to be installed in a manner similar to that described for Conditions II and III. Interior wall shielding is assumed to be covered with painted gypsum wallboard on steel studs tack-welded to the steel panels. Floor welds are to be ground smooth prior to the installation of vinyl asbestos tile, and the acoustical tile ceiling is to be suspended from rods welded to the shield along its lines of support.

As with Sub-Condition IIIa, Condition IVa assumes concrete block rather than poured-in-place concrete exterior wall construction. As a consequence, toggle or expansion bolts are to be used to attach the 1/4 by 4 inch bars to the existing walls. Otherwise, the architectural details and finishes are identical to Condition IV.





**FIGURE 30. CONDITION IV/IVa
SHIELDING PLAN**



2






FIGURE 31. CONDITION IV/IVa
ISOMETRIC





**FIGURE 33. CONDITION IV/IVa
HORIZONTAL WALL DETAIL**



SECTION 5

COST ESTIMATES FOR WELDED SHIELDS

The Opinions of Probable Cost presented here (Tables 2 to 7) for the all-welded shields are based upon a series of assumptions discussed in Section 4 and a list of additional assumptions given in Appendix A.

One assumption is that the location of the C³ structure is in the Chicago Metropolitan Area, and local labor and material costs are used exclusively, as of December, 1979. Publications such as Engineering News Record, Dodge Reports, or Building Construction Cost Data published by R. S. Means Co., Inc. can be consulted for costs in other cities. The prices cited here are for average, conventional construction. Local variations in the labor supply required for EMP shield construction could affect the actual rates.

Appendix B contains the worksheets used to arrive at the Opinions of Probable Cost in Tables 2 to 7. The individual costs listed in Appendix B are the costs to the General Contractor. To these, have been added ten percent for contractor's overhead, ten percent for contractor's profit, and a five percent contingency, in arriving at the totals given in Tables 2 to 7.

The cost of acquisition of land, or of an existing building to be retrofitted, are considered to be beyond the scope of this report, as are taxes. As indicated in the description of Conditions III and IV, it is considered unlikely that any substantial portion of the pre-existing HVAC, Electrical or Plumbing systems will be salvaged and re-used. For this reason, the Opinions assume the worst possible case of total replacement of these systems.

Finally, those costs of providing a shielded C³ structure NOT attributable to the costs of providing and installing the shield itself, are not included. Stated another way, the costs represent the premium to be paid for shielding an otherwise conventional C³ installation. It is assumed that those base costs to build the structure would be approximately \$475,000, or about \$39.50 per square foot. This figure includes the cost of the reinforced, poured-in-place concrete structure, interior walls (partitions), paint, false ceiling, and electrical, plumbing, heating and air conditioning facilities, as well as overhead, profit, and construction contingency. In comparing the total costs necessary to provide a completed, shielded C³ structure, this figure (\$475,000) should be added to the cost estimates for Conditions I and II in order to obtain a comparison of the acquisition costs for the four conditions. Such comparative totals are given in Section 9. (No provision has been made to consider the value of an existing building for which a shield is to be retrofitted, as in Conditions III and IV.)

TABLE 2 - OPINION OF PROBABLE COST - CONDITION I

<u>LABOR AND MATERIAL</u>	<u>HOURLY WAGE RATE</u>	<u>HOURS</u>	<u>DOLLARS</u>
Iron Worker (Field)	17.13	29,365	503,030
Iron Worker (Shop)	13.00	2,648	34,430
Painter (Field)	12.50	138	1,720
Carpenter (Field)	15.00	1,766	26,500
Material (Shielding)			122,270
Material (Other)			<u>1,140</u>
Subtotal			689,090
Contractor's Profit and Overhead (21%)			<u>144,710</u>
Subtotal			833,800
Contingency (5%)			<u>41,690</u>
Total			\$875,490
		SAY	\$875,000

TABLE 3 - OPINION OF PROBABLE COST - CONDITION II

<u>LABOR AND MATERIAL</u>	<u>HOURLY WAGE RATE</u>	<u>HOURS</u>	<u>DOLLARS</u>
Iron Worker (Field)	17.13	25,357	434,360
Iron Worker (Shop)	13.00	7,448	96,820
Painter (Field)	12.50	-	-
Carpenter (Field)	15.00	1,766	26,500
Material (Shielding)			153,325
Material (Other)			<u>7,500</u>
Subtotal			718,505
Contractor's Profit and Overhead (21%)			<u>150,886</u>
Subtotal			869,391
Contingency (5%)			<u>43,470</u>
Total			\$912,861
		SAY	\$910,000

TABLE 4 - OPINION OF PROBABLE COST - CONDITION III

<u>LABOR AND MATERIAL</u>	<u>HOURLY WAGE RATE</u>	<u>HOURS</u>	<u>DOLLARS</u>
Iron Worker (Field)	17.13	24,185	414,300
Iron Worker (Shop)	13.00	5,864	76,230
Painter (Field)	12.50	1,360	17,000
Carpenter (Field)	15.00	3,330	49,950
Electrician (Field)	17.00	2,837	48,230
Plumbing (Field)			
Sheet Metal (Field)	Av. 15.90	6,478	103,000
Steam Fitters (Field)			
Laborer (Field)	12.00	5,742	68,900
Material (Shielding)			143,600
Material (Other)			224,300
Subtotal			1,145,510
Contractor's Profit and Overhead (21%)			240,560
Subtotal			1,386,070
Contingency (5%)			69,300
Total			\$1,455,370
		SAY	\$1,455,000

TABLE 5 - OPINION OF PROBABLE COST - CONDITION IIIa

<u>LABOR AND MATERIAL</u>	<u>HOURLY WAGE RATE</u>	<u>HOURS</u>	<u>DOLLARS</u>
Iron Worker (Field)	17.13	24,814	425,060
Iron Worker (Shop)	13.00	7,242	94,140
Painter (Field)	12.50	1,360	17,000
Carpenter (Field)	15.00	3,330	49,950
Electrician (Field)	17.00	2,837	48,230
Plumbing (Field)			
Sheet Metal (Field)	Av. 15.90	6,478	103,000
Steam Fitters (Field)			
Laborer (Field)	12.00	5,742	68,900
Material (Shielding)			160,070
Material (Other)			224,300
Subtotal			1,190,650
Contractor's Profit and Overhead (21%)			250,040
Subtotal			1,440,690
Contingency (5%)			72,030
Total			\$1,512,720
		SAY	\$1,515,000

TABLE 6 - OPINION OF PROBABLE COST - CONDITION IV

<u>LABOR AND MATERIAL</u>	<u>HOURLY WAGE RATE</u>	<u>HOURS</u>	<u>DOLLARS</u>
Iron Worker (Field)	17.13	33,854	579,920
Iron Worker (Shop)	13.00	7,262	94,410
Painter (Field)	12.50	1,350	16,870
Carpenter (Field)	15.00	3,991	59,870
Electrician (Field)	17.00	2,837	48,230
Plumbing (Field)			
Sheet Metal (Field)	Av. 15.90	6,478	103,000
Steam Fitters (Field)			
Laborer (Field)	12.00	4,307	51,680
Material (Shielding)			185,010
Material (Other)			240,090
Subtotal			1,379,080
Contractor's Profit and Overhead (21%)			289,600
Subtotal			1,668,680
Contingency (5%)			83,420
Total			\$1,752,100
		SAY	\$1,750,000

TABLE 7 - OPINION OF PROBABLE COST - CONDITION IVa

<u>LABOR AND MATERIAL</u>	<u>HOURLY WAGE RATE</u>	<u>HOURS</u>	<u>DOLLARS</u>
Iron Worker (Field)	17.13	33,904	580,770
Iron Worker (Shop)	13.00	10,530	136,890
Painter (Field)	12.50	1,350	16,870
Carpenter (Field)	15.00	3,991	59,870
Electrician (Field)	17.00	2,837	48,230
Plumbing (Field)			
Sheet Metal (Field)	Av. 15.90	6,478	103,000
Steam Fitters (Field)			
Laborer (Field)	12.00	4,307	51,680
Material (Shielding)			209,910
Material (Other)			240,090
Subtotal			1,447,310
Contractor's Profit and Overhead (21%)			303,940
Subtotal			1,751,250
Contingency (5%)			87,550
Total			\$1,838,800
		SAY	\$1,840,000

SECTION 6

DESIGN FOR SHIELD FASTENED BY POWDER-DRIVEN PINS

6.1 INTRODUCTION

At the conclusion of the study and costing of the welded shield design (Sections 3, 4, and 5), it was evident that a substantial portion of the shield cost was due to the MIG welding of the shield seams. Consequently, as a possible means of providing a lower cost shield, an alternative design was considered which, except for the entry plate, does not utilize welding to fasten the steel sheets together. The alternative design considered uses powder-driven pins which serve both functions of fastening the sheets together mechanically and fastening the sheets to the building's concrete walls, floor, and roof. For practical purposes, the powder-driven pins can be considered to fasten the sheets together with about the same characteristics as would be provided by bolts or rivets. This section of the report describes the features of the design; Section 7 presents a cost estimate.

The basis for considering this alternative design is the report⁶ of a recent study by SRI International on bolted lapped-joint EMP shields. The study showed that good overlap joints can be made for EMP shields using aluminum or galvanized steel if the panels have good metal-to-metal contact, if fastener spacings are no larger than 7.5 cm (3 inches), and if joint overlap is at least 10 cm (4 inches).

Since the alternative design considered here was evolved near the conclusion of the present program, only limited time and effort could be applied. As a result, the design is much less detailed than the designs for the welded shield, and the cost figures provided must be considered to be only a rough estimate.

It must also be emphasized no experimental evidence is available regarding the shielding effectiveness of a total facility shield of this type. Also, as will be pointed out, the practicality of this type of construction for the floor shield is not at all certain. Furthermore, while this type of construction eliminates the welding requirements for most of the shield, an entry plate consisting of 1/4 inch steel sheets welded together, is retained on the end of the building through which all the penetrants are assumed to enter.

6.2 GENERAL DESCRIPTION

The proposed shield consists of galvanized steel sheets, primarily 4 feet by 8 feet, covering the inner surfaces of the exterior walls, roof, and floor. As shown in Figure 34, the edges of adjacent sheets would be overlapped four inches, and the sheets would be fastened together, as well as attached to the building surfaces, by powder-driven pins




Figure 34. SHIELD DESIGN FOR CONDITION V

every three inches along each overlapped seam. After the complete shield is emplaced in this manner, all of the seams would be lightly grit blasted to remove any surface dirt, and the seams would be arc sprayed with zinc to provide electrical continuity between sheets.

In the welded-shield design (Sections 3, 4, and 5), 11 gauge (0.12 inch or 3.0 mm) steel was proposed to prevent the sheets from buckling during welding. For the alternative design considered here using powder-driven pins, that restriction is removed, and thinner material can be used. Two shield thicknesses are considered:

14 gauge (0.075 inch or 1.9 mm), and
18 gauge (0.048 inch or 1.2 mm).

By reference to Fig. 7, it is seen that the absorption loss for 14 ga and 18 ga steel is approximately 120 dB and 80 dB, respectively at 10 KHz. The mechanical designs for the two shield thicknesses are assumed to be the same. The only difference considered is the difference in cost of the material, essentially due to the difference in weight of the sheets: 105 lb./sheet for 14 ga; 69 lb./sheet for 18 ga.

6.3 SOME CHARACTERISTICS OF POWDER-DRIVEN PINS

The powder-driven pins are made of galvanized steel. They are available in various shank diameters from 1/8 to 1/4 inch and shank lengths from 1/2 to 2 1/4 inch. One end of the shank is tapered for penetrating the steel, concrete, etc., while the other end is available in various configurations such as a threaded end, an eyelet end, or a flat-headed end (optionally with an additional metal washer).

The pins are installed or driven using a hand-held, gun-shaped tool. The barrel accommodates the pin which is to be driven, and an explosive charge of gun powder. Firing is accomplished by pressing the muzzle of the barrel against the work surface, and squeezing the trigger. With an automatic tool, pins can be driven at a fairly rapid rate, with rates of six to ten per minute quoted by suppliers.

For pins driven into concrete, as anticipated here for the shield, maximum holding strength in the concrete occurs when the penetration into the concrete is approximately eight times the shank diameter. For 1/8 inch diameter pins, a one inch length should be suitable for fastening the sheets to the concrete walls, floor, and ceiling. The holding force depends strongly on the characteristics of the concrete, including the compressive strength, the type of aggregate, and whether the cement mixture is vibrated after it is poured. Pins with 1/8 inch diameter shank driven into concrete having a compressive strength of 2500 psi can have an average holding strength of approximately 500 to 900 pounds per pin. Thus it appears that such pins should provide adequate support to fasten the steel sheets to the concrete. To assure that the pins driven into concrete

that the pins driven into concrete maintain their holding power constant over a long period of time, e.g., 20 years, it is recommended that they be installed in concrete which has cured for a minimum of 28 days.

Uniformity of depth of pin penetration will depend on the uniformity of the concrete. Soft regions such as sand spots could permit excessive penetration, with the result that the head of the pin may be driven right through the sheets being fastened, putting a hole in the sheet.

For attachment of ceiling hanger straps to support a false ceiling, lighting fixtures, conduits, etc., additional powder-driven pins could be installed in the ceiling on 16 inch centers. Pins with eyelet holes could be used for accommodating hanger wire directly.

6.4 GRIT BLASTING

Prior to arc spraying of zinc on the exposed sheet metal seams, it is recommended that the region along the seams be lightly grit blasted to remove any surface dirt or grease. The floor must be swept and probably vacuumed prior to application of the zinc arc spray.

6.5 ZINC ARC SPRAYING

While the powder-driven pins can provide good mechanical fastening of adjacent steel sheets to each other, the mechanical attachment alone cannot be relied on to provide good electrical continuity. Even a small amount of "dimpling" of the sheets at each pin location will cause the sheets to bow slightly, possibly preventing even good mechanical contact along much of the seam. In addition, in the region of the pins, where the sheets are held in firm mechanical contact, electrical contact may still be poor because of surface dirt on the mating surfaces. In order to provide good electrical contact between sheets, and therefore low resistance across seams, arc spraying of the seam with a layer of zinc is proposed.

Commercial equipment to perform metallic arc spraying consists primarily of an arc spray gun, a high-current power supply, and a source of compressed air. Two bare wires of the metal to be sprayed are electrically isolated except for contact near the nozzle of the gun, where their ends are in contact. The power supply, connected between the two wires, causes current flow at the junction of the wires, causing the wire tips to melt. A continuous jet of air blows the molten metal as a fine spray out of the gun's nozzle. As the metal spray is deposited on the surface to be coated, a dense integrally bonded coating builds up.

The sprayed zinc is said to have a density equal to 94 percent of the density of solid zinc. (It contains a slight amount of oxidation products.) The conductivity of sprayed zinc is reported to be less than that of solid zinc, but greater than that of steel.

To estimate the amount of zinc required to cover a surface to a specified depth, a guide is that 0.9 ounce of zinc is required to cover one square foot of surface to a depth of 0.001 inch. A typical commercial arc spray machine is capable of spraying zinc at an average rate of 36 pounds/hour.

6.6 PROBLEMS ASSOCIATED WITH THIS SHIELD DESIGN

Perhaps the major questions regarding the applicability of powder-driven pins for the shield fabrication relate to the floor shield. One possible problem is the lack of a smooth surface due to the heads of the pins protruding above the surface of the steel sheets. This roughness would probably make it impossible to apply directly a thin plastic floor covering, e.g., vinyl.

Another problem might possibly arise in regard to the shielding performance. Floor loading might affect the electrical continuity of the floor shield if it causes fracturing of the arc-sprayed zinc seams over a period of time. Such fracturing may possibly occur due to constant heavy loading on portions of the floor, e.g., by heavy equipment or internal walls, or else possibly by varying loads and resulting flexing, for example due to repeated walking over the seams.

If satisfactory answers cannot be found for these questions, it may be necessary to require the use of a welded steel floor as provided in the designs in Sections 3 and 4 of this report.

SECTION 7

COST ESTIMATE FOR SHIELD FASTENED BY POWDER-DRIVEN PINS

Table 8 shows the cost estimate for the shield design designated here as Condition V -- New Construction, Internal Shield, Galvanized Steel Sheets Fastened by Powder-Driven Pins. A more detailed listing is given in Appendix B. As mentioned earlier, the design features and cost estimate for Conditions V were developed by IITRI near the end of the contract and were not done in the same degree of detail as were the designs and cost estimates developed by L. B. Knight for Conditions I, II, III, and IV. The assumptions made in costing the shield design for Condition V are given below.

7.1 GALVANIZED STEEL SHEET

Material costs for flat stock:

14 ga	48 inches x 96 inches, flat sheets, 105 pounds at \$28.25/100 pounds = \$30/sheet
14 ga	48 inches x 96 inches and 30 inches x 96 inches, formed sheets (predominantly a single bend) \$40 est.
18 ga	48 inches x 96 inches flat sheets, 69 pounds at \$29.00/100 pounds = \$20/sheet

Labor Costs: The labor costs for installing the steel sheets were based on the estimated time required to install the powder-driven pins used for attaching the sheets to the concrete. With an average seam length of 12 feet per sheet (4 feet on one edge, 8 feet on the other), with four pins per foot of seam, 48 pins are required per sheet.

It is estimated that pins could be installed at an average rate of 6 pins per minute, thus requiring 8 minutes for one sheet. Some additional time is required for initially positioning the sheet properly, etc. A total installation time of 20 minutes per sheet is allocated. On this basis, the time required for installing the total of 1808 sheets for the entire shield would be 603 hours.

A five-man installation crew was assumed:

- one man driving pins
- two men positioning and holding the steel sheets
- one man carrying materials
- two men, half time, positioning the moveable scaffold

Therefore the total man-hours = $603 \times 5 = 3015$. Assuming an average wage of \$16/hour, the total labor cost (for installing 1808 sheets) is $3015 \times \$16 = \$48,240$, or \$27 per sheet.

TABLE 8
COST ESTIMATE FOR CONDITION V

Galvanized Sheet (Material) 14 ga	62,240 [†]
Galvanized Sheet (Labor)	48,816
Powder-Driven Pins	29,750
Grit Blasting	7,500
Shielded Doors	26,500*
Zinc	12,290
Zinc Arc Spraying (Labor)	12,240
Ceiling Hangers (Material)	7,500*
Ceiling Hangers (Labor)	4,000
Penetrations	29,500*
1/4 inch Entry Plate	<u>27,530*</u>
	267,866
Contractor's Profit and Overhead (21%)	<u>56,252</u>
	324,118
Contingency (5%)	<u>16,206</u>
	340,324
	≈ 340,000

[†]Approximately \$44,000 for 18 ga material

*Cost items identical with those of the all-welded shield designs.

7.2 FASTENING PINS

Estimated total number of pins for 1372 sheets 48 inches x 96 inches, and 436 sheets 30 inches x 96 inches \approx 85,000. Cost is estimated at \$0.35 per pin, or a total of \$29,750.

7.3 GRIT BLASTING OF SEAMS

Total seam length = 21,042 feet

Assume a 3-man crew blasts 200 feet of seam/hour, requiring 100 hours, or 300 man-hours.

Assume \$25/man-hour for labor, equipment, and materials, or a total of \$7,500.

7.4 SHIELDED DOORS

Itemized costs are listed in Appendix B, Condition V.

7.5 ZINC ARC SPRAYING

Total seam length = 21,042 feet

Seam width = 3 inches = 1/4 foot

Seam thickness = 1/32 inch = 0.031 inch

Seam area = 5,260 ft.²

Seam volume = 5,260 ft.² x 31 mils

Required weight of zinc = 0.9 ounce for area 1 ft.² by 1 mil

Therefore zinc required for seams =

$$0.9 \text{ ounce} \times 5,260 \times 31 = 146,754 \text{ ounces} = 9,172 \text{ pounds}$$

Application rate = 36 pounds/hour (est).

Therefore total application time = 255 hours.

Only one man is required for arc spraying.

Assume two men positioning a moveable scaffold and carrying materials.

Labor: 255 hours x 3 x \$16/hour (ave.) = \$12,240

Material: Cost of zinc = 9,172 pounds x \$1.34/pound = \$12,290

7.6 CEILING HANGERS

Material: 7,500 hangers at \$1 ea. (est.) = \$7,500

Labor: Assume 1 hanger per minute is installed by a crew of 2, requiring 125 hours, or 250 man-hours, at \$16/man-hour, or \$4,000.

7.7 PLATE, 1/4 INCH

Estimates based on L. B. Knight data for Conditions I, II, III, IV.

7.8 PENETRATIONS

L. B. Knight estimate for Conditions I, II, III, and IV is used here.

SECTION 8

SHIELD QUALITY CONTROL, EFFECTIVENESS TESTS, AND MAINTENANCE COSTS

8.1 INTRODUCTION

The costs of assuring proper shielding effectiveness of the C³ facility can be grouped as follows:

- Quality control during construction
- Testing the facility for initial performance certification
- Periodic inspection and maintenance.

A discussion of each of these items, along with cost estimates, are given below. A summary including the total cost estimate based on a 20 year shield lifetime, is given in Table 9. These results do not include costs of any required reworking of defective seams, as no information is available on the frequency of occurrence of such defects.

8.2 QUALITY CONTROL DURING CONSTRUCTION

8.2.1 Testing of Steel Samples

Laboratory tests of samples of the steel sheets should be made to measure the conductivity, the low-field permeability (non-saturating), and the saturation characteristic. Suitable test procedures have been described.⁷ While the steel sheets are not procured to a conductivity or permeability specification, suitable conductivity and permeability characteristics are of such importance that it is felt to be desirable to perform laboratory tests on representative samples from the same mill run as the plates to be used to assure that the shield will have the desired attenuation properties. Effort is estimated at 80 man-hours at \$30 per man-hour, including overhead, for instrumentation set-up and testing time, for a total of approximately \$2,400.

8.2.2 Floor Plates at Perimeter Wall

For Condition I, New Construction, External Shield, it is necessary for the pre-fabricated steel floor shield plates (on top of the floor slab) to pass through the perimeter walls to be welded to the exterior wall shield. The construction design provides for 520 linear feet of 11 ga steel plate penetrated by steel reinforcing rods welded to it. Time to factory inspect welds is estimated at 8 man-hours, at \$15 per man-hour, or a total of \$120. This item is negligible compared with other items.

8.2.3 Seams, Plug Welds, and Conductor Penetrations

Quality control of welds during construction will consist of supervision and careful visual inspection of all welds. Magnetic inspection techniques such as magnafluxing are not considered necessary. While the time and costs will depend on the total linear footage of seams and the number of plug welds, they will not necessarily be proportional since an on-site inspector will be able to supervise and inspect the work of a number of welding crews or pin-driving crews working in parallel. It is estimated that approximately 1,000 man-hours of inspection time would be required at a cost of approximately \$30/man-hour, or a total of \$30,000. This same estimate is assumed for Condition V (use of powder-driven pins) as well as for the welded-seam construction.

8.3 INITIAL PERFORMANCE CERTIFICATION

A series of performance certification tests are recommended using

- 1) The Shielded Enclosure Leak Detection System (SELDS) which uses current injected directly onto the enclosure walls
- 2) Small antennas to illuminate the enclosure walls.

First, each of these types of tests is described briefly. Then an outline of a test program is given.

8.3.1 SELDS Testing⁸

This type of test, often referred to as the Seam Sniffer Test, employs CW current at a frequency of approximately 100 kHz injected directly onto the outer walls of the shielded enclosure (See Figure 35). A small, calibrated detector probe, designed to measure the magnetic field leakage component perpendicular to the shield wall, is moved along each seam on the interior of the enclosure. A defective seam in the shield produces an increase in the measured field if the direction of the seam is such as to disrupt the flow of current on the surface of the shield. In order to assure that a proper directional relationship will be achieved, it is necessary to perform three separate tests, each with the current applied from a different pair of diagonally opposite corners (See Figure 35).

The magnetic pickup coil of the detector is moved along the seam as the detector output (visual and audible) is observed. A commercially available SELDS equipment has as 0-140 dB shielding effectiveness measurement range. For the present purpose of estimating the cost of testing, it is assumed that the seam can be scanned at a rate of one foot per second where the seam is within easy reach (floor and lower portion of walls), and half that rate for the more difficult areas (internal ceiling shield and upper portion




Figure 35. PLACEMENT OF FEEDWIRES FOR SELDS
TESTING OF SHIELDED FACILITY

of walls).

In customary application to shielded enclosures, the SELDS current is applied to the exterior surface of the shield, and the seams on the interior surface are scanned. This procedure would generally be applicable here, except for Condition I (Exterior Shield), where the seams will not be available on the inside of the facility. In this case it would appear preferable to apply the current to the inner surface of the shield (through electrical leads brought through the concrete wall to the inside of the building) and scan the seams on the exterior.

The SELDS is usually applied to a shielded enclosure having the shape of a rectangular parallelepiped. The C³ facility shields for Conditions I, II, III, and V approximate that shape except for entry and exit vestibules, etc., and the SELDS technique should provide useful results over the structure as a whole. In addition, it will be necessary to apply the SELDS to four individually shielded regions:

- 1) the communications entry vault,
- 2) the electrical power entry vault,
- 3) the storage area,
- 4) personnel entry vestibule.

For Condition IV (Internal Shield, Retrofit, Interior Walls Retained), the shield follows both surfaces of all interior walls. As a result, current applied to diagonally opposite extremities of the building will flow very irregularly on the shield surfaces. In regions where the current flow is sparse, the applied magnetic field intensity is low, and the detection system loses sensitivity. Consequently, a test using current injection at the building corners might not provide a 100 dB test of the shield on the interior walls because of the peculiar current distribution. It is possible that the total current injected onto the shield will also be small because of the impedances of the irregular shield envelope. It may be desirable to attempt measurements by injecting current at the corners of each of the four operational rooms. However, it should be emphasized that each room is not totally enclosed by a shield (doorway is unshielded), and therefore, such a test may not be conclusive.

8.3.2 Small-Antenna Radiation Testing

It has been shown elsewhere⁹ that the SELDS or Seam Sniffer results, obtained at 100 kHz, cannot be used to provide an estimate of shielding effectiveness at widely removed frequencies. Therefore, for the present requirement for shielding effectiveness over the range 10 kHz to 100 MHz, additional tests are required, and tests based on MIL-STD-285 are recommended. Specifically, tests such as the following are suggested:

- Magnetic Field tests, using small-loop antennas, at frequencies of 10 kHz, 100 kHz, 1 MHz, 10 MHz
- Electric Field tests, using monopole antennas, at frequencies of 10 MHz, 100 MHz

Measurements should be made at the center and at each corner of all doors, center of all air vents, and at a representative number of points along each outer wall, and possibly on the ceiling shield. Measurements are required on the portions of the envelope shielding the facility as a whole, the communications entry vault, the power entry vault, the storage area, and the personnel entry vestibule.

In general, no special difficulties are foreseen in applying these MIL-STD-285 type tests to shield configurations for Conditions I, II, III, or V. However, for Condition IV (Internal Shield, Retrofit, Interior Walls Retained), the shield is on both surfaces of all interior walls. Therefore it will not be possible to gain access to two locations--one for a transmitting antenna and one for a receiving antenna--on opposite sites of these parts of the shield. Consequently, this type of test would not appear to be applicable for those portions of the shield.

8.3.3 Outline of Certification Test Program

The following types of tests are recommended for the initial performance certification:

- (1) SELDS tests, prior to addition of interior walls, wall covering or floor covering, or welding of steel hangers from internal ceiling shield (for conduit, false ceiling, etc.)
- (2) MIL-STD-285 type tests, again, prior to addition of interior walls, wall coverings, steel hangers, etc.
- (3) Initial benchmark tests using SELDS and MIL-STD-285 type tests but with the detector used for exploring and measuring the fields in the interior volume of the building, not at the wall as in (1) and (2) above. These tests would also be performed prior to addition of interior walls, steel hangers, etc.
- (4) Secondary benchmark tests, similar to those in (3) above, but after the addition of interior walls, steel hangers, false ceiling, etc., and the installation of all operational equipment, cabling, etc. The purpose of the secondary benchmark tests is to provide a set of baseline data against which subsequent test data -- to be obtained during the 20 year shield lifetime -- can be compared to detect any changes in shielding performance.

Costs of labor for testing are estimated to total approximately \$11,000 as shown in Table 9. Within the uncertainty of the estimation, this total is considered to apply to each of the five shield configurations. It should again be mentioned that the procedures for testing the shield for Condition IV are somewhat indeterminate due to the extensive shielding on both sides of all interior walls.

8.4 PERIODIC INSPECTION AND MAINTENANCE

The main requirements for inspection, testing, and maintenance are estimated as follows:

- Doors:
- (a) inspect weekly, one man-hour total for 5 doors
 - (b) clean monthly, including vacuuming the recesses;
8 man-hours total for 5 doors
 - (c) test semi-annually: 40 man-hours total for 5 doors.
- Replacement:
- (a) Two hinged doors at Main Entrance; replace every 5 years
Cost ea: \$2,000 material, \$500 labor; \$5,000 total
 - (b) One hinged door at Emergency Exit and two hinged doors in Entry Vault; replace after 10 years
Cost ea: \$2,000 material, \$500 labor; \$7,500 total
 - (c) Two sliding doors in Storage Room: replace every 5 years
Cost ea: \$6,000 material, \$1,000 labor; \$14,000 total

Recheck of Secondary Tests: Spct-test semiannually; two man weeks.

Using \$10 per man-hour for the routine items of inspection, maintenance, and testing, and including the estimated door replacement costs, the total maintenance cost for a 20-year shield life is estimated as \$142,500.

8.5 TOTAL COSTS FOR SHIELD QUALITY ASSURANCE AND MAINTENANCE

From the previous cost estimates for quality control during construction, the performance of certification tests, and the periodic inspection, testing, and door replacement, the total costs for a 20-year shield life are estimated at \$186,000.

It should be noted that all tests described here for the completed shield employ only low-level, continuous-wave test signals. Based on past experience¹⁰ it was estimated that the cost of testing a large shielded facility using a high-level pulse simulating an EMP radiation would be approximately \$500,000 (in 1975).

TABLE 9
COSTS FOR SHIELD QUALITY CONTROL,
TESTING, AND MAINTENANCE

Quality Control During Construction

Testing steel samples	\$ 2,400
Inspection of perimeter floor plates	120
Weld inspection	<u>30,000</u>
	32,520

Initial Performance Certification

Initial SELDS tests	2,500
Initial MIL-STD-285 tests	2,500
Initial Benchmark tests	3,000
Secondary Benchmark tests	<u>3,000</u>
	11,000

Periodic Inspection and Maintenance

Weekly inspection of doors	10,000
Monthly cleaning of doors	20,000
Semiannual tests of doors	16,000
Door Replacement	
Two hinged doors after 5, 10, 15 yrs.	15,000
Three hinged doors after 10 yrs.	7,500
Two sliding doors after 5, 10, 15 yrs.	42,000
Semiannual recheck of Benchmark tests	<u>32,000</u>
	142,500

186,020

SECTION 9

CONCLUSIONS AND RECOMMENDATIONS

The shielding cost estimates for the various construction options considered are tabulated in Table 10. For the welded shield designs, costs for shield construction and quality assurance for conditions I and II (New Construction) are estimated to be slightly greater than \$1,000,000. If the cost of the new building is added, the total is slightly greater than \$1,500,000 -- approximately \$100,000 less than the shield costs for retrofitting an existing building, with removal and replacement of interior walls (Condition III). Costs for Condition IV, retrofit with interior walls retained, are approximately \$2,000,000. A very substantial portion of the costs for all these configurations is due to the high cost of MIG welding of the shield seams.

In regard to the all-welded designs, the total costs for Conditions I, II, and III are similar, if the cost of the new building is included for Conditions I and II. Condition IV is the least attractive from the viewpoint of cost, and should be considered only when required by other factors.

To begin with, in Condition IV (retrofit, partitions are to remain in place), it is clear that a high premium is paid for additional labor and material. The amount of shielding required is greater. The cost of labor is increased not only by the increase in shielding, but by the necessity of working within a constrained environment which involves logistical problems for the Contractor. Also, retrofit conditions always carry an unknown factor; even an extensive survey of existing conditions may fail to uncover problems which may subsequently affect construction costs. Additionally, the savings involved in retaining interior partitions are more than offset by the costs involved in providing a completed, habitable, shielded C³ structure.

Shielded walls and floors are assumed to be recovered with painted gypsum wallboard and vinyl-asbestos tile, respectively. Ceilings, necessarily removed to install shielding, have to be replaced along with above-ceiling ductwork. It is considered unlikely that light fixtures or electrical conduit will be salvaged and re-installed. The existing heating/air conditioning plant has to be removed in order to install the shielding. For purposes of this report, it was considered unlikely that the condition of old equipment and plumbing fixtures would justify reinstallation. The Owner is left with a situation in which only the building shell and interior partitions (assuming that they run from floor to roof slab) are re-used. Offset against the savings are the labor and material costs for both shielding and new Architectural/Mechanical/Electrical work.

TABLE 10

Condition	Building and Shield	Shield Location	Shield Fabrication	Estimated Costs				Total
				Shield Construction	Quality Assurance ^{5,6}	Shield Subtotal	New Building	
I	New	Exterior	Welded	875,000	186,000	1,061,000	475,000	1,536,000
II	New	Interior	Welded	910,000	186,000	1,096,000	475,000	1,571,000
III ¹	Retrofit	Interior	Welded	1,455,000	186,000	1,641,000	-	1,641,000
IIIA ²	Retrofit	Interior	Welded	1,515,000	186,000	1,701,000	-	1,701,000
IV ³	Retrofit	Interior	Welded	1,750,000	186,000	1,936,000	-	1,936,000
IVA ⁴	Retrofit	Interior	Welded	1,840,000	186,000	2,026,000	-	2,026,000
V	New	Interior	Powder-Driven Pins	340,000 ⁶	186,000	526,000	475,000	1,001,000

NOTES: 1. Poured concrete building; interior walls removed and replaced.

2. Concrete block building; interior walls removed and replaced.

3. Poured concrete building; interior walls retained.

4. Concrete block building; interior walls retained.

5. Includes shield testing and door replacement for 20 years; no weld rework

6. IIIRI estimates; others are LBK estimates.

Condition III (retrofit, partitions removed and replaced) is considered to be somewhat more advantageous. Some cost savings are to be achieved through a reduction in the amount of shielding, less constrained working conditions, and a consequent reduction in labor and material costs. On the other hand, all of the costs for new architectural/mechanical/electrical work cited will be incurred. Added to these will be the costs of new partitions with their electrical conduit and outlets.

Conditions IIIa and IVa (retrofit, concrete block exterior walls) are considered to be less desirable than a cast concrete building shell. The necessity to predrill the 1/4 by 4 inch attachment bars and the concrete block prior to inserting toggle bolts is costly. All of the previously cited costs (and potential unknowns) also apply to these alternatives.

It is, therefore, considered that retrofit installations are to be avoided if possible. The savings involved in re-using an existing structure are, in this particular type of re-cycling, offset by the unusually large labor and material cost required to result in a habitable building. It should be noted the cost of shielding a building in the cheapest manner (new construction), amounts to twice the cost of actually building the (unshielded) C³ facility. By comparison, the cost of shielding an existing building is three times the cost of a new, unshielded building, and approximately the same as the cost of a completely shielded, new C³ installation. In conclusion, no significant savings are realized in retrofitting an existing building, and it may even cost more than totally new construction.

In comparison of the two shield designs for new construction, Condition I (exterior shield) is most subject to climatic influences. Extreme cold makes an already sophisticated welding process more difficult. Extreme heat makes exposed metal-skinned buildings substantially more difficult to cool. Condition I also requires relatively more highly skilled labor, in that the welds are exposed to view. Periodic maintenance is also a consideration. The last three problems could be alleviated by covering the exterior wall shielding with an architectural veneer. While that would result in, among other things, a more pleasing looking structure, it would introduce problems of its own. Among them would be devising a means of attaching the veneer to the shielding. It would also increase construction cost.

For these reasons, Condition II (new construction, interior shielding) may, under many circumstances, be considered to be more advantageous. While it involves more shielding, and is, therefore, slightly more costly, the shielding is protected from both view and weather. Moreover, the interior shielding can be installed and function independently of climatic conditions. Condition II is therefore considered to be less problematical to a wide range of geographical applications.

Finally, there are two factors which can influence all of the Conditions in a manner disproportionate to their present cost relationships. These factors are (1) the ready availability of materials, and (2) local labor rules. They relate directly to the amount of shielding material and the consequent amount of welding labor.

As an alternative to an all-welded shield, the use of powder-driven pins for fastening the steel sheets, and zinc arc-spraying of the seams (Condition IV) appears to be approximately \$500,000 less costly than the all-welded designs of Conditions I, II, and III. However, in comparing this estimate with those for the welded designs, the following observations should be kept in mind: (1) the design for Condition V is less detailed and the cost estimate more approximate than for the welded designs; (2) no experimental evidence is available regarding the shielding effectiveness of a building shield with this type of seam; (3) the protrusion of pin heads on the floor seams, as well as the uncertainty of the integrity of the floor shield under expected weight loads, may require a welded floor shield, with an additional cost of perhaps \$100,000. It is recommended that experimental work be undertaken to evaluate the performance of a shield of this type, with particular emphasis on the required design of the floor shield and on the long-term integrity of the shield, including the effect of heavy or variable floor loading.

SECTION 10

REFERENCES

1. Project 85, EMP Study, Supreme Headquarters Allied Powers Europe, Brussels, Belgium, p. 15, p. 20.
2. Cowdell, R. B., The Effect of Changing Frequency and Field Intensity on the Permeability of Ferrous Materials, pp. 102-112, 1970 EMC Symposium Record, July 1970.
3. Ferber, R. R. and Young, F. J., The Shielding of Electromagnetic Pulses by Use of Magnetic Materials, 1969 IEEE EMC Symposium Record, pp. 73-79, June 1969.
4. Ferber, R. R. and Young, F. J., Enhancement of EMP Shielding by Ferromagnetic Saturation, IEEE Trans. on Nuclear Science, Vol. NS-17, No. 6, pp. 354-359, December 1970.
5. Young, F. J., Ferromagnetic Shielding Related to the Physical Properties of Iron, 1968 IEEE EMC Symposium Record, pp. 88-95, July 1968.
6. Bolted Lapped - Joint EMP Shields, Report DNA 4472-F, SRI International, Contract DNA001-76-C-0386, June 1977.
7. Brush, D. R., Schulz, R. B., and Jorgensen, L., Low Frequency Electrical Characteristics of RF Shielding Materials, IEEE Trans., Vol. EMC-10, pp. 67-72, March 1968.
8. Lockwood, R. O., New Technique for the Determination of the Integrity of Shielded Enclosures by the Measurement of the Perpendicular Magnetic Field, pp. 61-69, 1967 EMC Symposium Record, July 1967.
9. Bridges, J., Formanek, V., and Toullos, P., Limitations of Seam Sniffer Techniques to Estimate Shielding Effectiveness Over a Broad Frequency Range, First Annual Nuclear EMP Meeting, Air Force Weapon Laboratory, Albuquerque, New Mexico, September 1973.
10. Safeguard EMP/RFI Lessons Learned, Vol. I, U. S. Army Corps of Engineers. Huntsville, Alabama, Report HNDSP-75-350-ED-SR; 31 December 1975.

APPENDIX A
FACTORS AFFECTING THE OPINIONS
OF PROBABLE COST FOR THE ALL-WELDED SHIELD DESIGNS

FACTORS AFFECTING THE OPINIONS OF PROBABLE COST
FOR THE ALL-WELDED SHIELD DESIGNS

1. All 5' by 10' or 6' by 10' plates have two (2) interior rows of five (5) 1/2" diameter holes each, except for the walls, which have two (2) interior rows of eight (8) 1/2" diameter holes each.
2. All vertical steel reinforcing bars that penetrate the floor plates at interior columns and perimeter walls are welded to horizontal plates. Each bar is welded to both the upper and lower surface of the plate.
3. All beams in the 60' direction are 12" by 24".
4. All beams in the 200' direction are 20" by 24".
5. All interior columns are 20" by 20".
6. All columns and beams have been deleted from the perimeter walls.
7. All pre-punched holes in the shielding are 1/2" diameter.
8. All concrete-imbedded plates (4" wide by 1/4" thick and 2" by 2" by 1/8" angle) will be delivered with 1 3/8" by 4" long Nelson studs welded to them at 2'-0" o.c. and pre-drilled with nail holes spaced at 2'-0" o.c. in a staggered pattern.
9. All continuous welding is priced midway between the cost of an easy and difficult operation which would be required to level the scheduled surfaces.
10. Grinding of welds will be required on exterior walls for the exterior wall Condition I, and for floors in all Conditions.
11. Grinding of welds for interior shielding will not be required except for floors.
12. Documents concerning the concrete work are to stress rigid concrete insert requirements.
13. Beam ceiling plates, for new construction interior shielding, will be horse shoe-shaped with four (4) rows of five (5) 1/2" diameter holes, each welded to four (4) rows of 4" wide by 1/4" thick plate.
14. Cost of installing angles and plates to concrete forms is to be included in estimate.
15. All costs used were derived from costs given by U.S. Steel, Inland Steel, Ryerson Steel, the Zack Co., Reliable Welding, and Ralph Simpson Co.
16. All prices are based on conditions that occur in Chicago, IL as of 12/14/79, without any contingencies or escalation as stated by the firms listed in 15 above.
17. Five (5) single-leaf swing doors with shielding applied have been included in all Conditions.
18. Two shielded sliding doors, to be used on the storage room, have been included for all Conditions.

19. Ceiling hangers have been included at 20 by 24 inch centers.
20. In Conditions III and IV, interior partitions are assumed to be gypsum wall board on metal studs.
21. Existing exterior doors, not to be shielded, are to be retained.
22. No acquisition costs are included for land or existing building.
23. Costs include demolition in Conditions III and IV, and total replacement costs for HVAC, Electrical and Plumbing Systems.
24. No architectural/engineering costs are included.
25. Costs for scaffolding have been included,

APPENDIX B
DETAILED LISTS OF SHIELD CONSTRUCTION COSTS

APPENDIX B

LESTER B. KNIGHT & ASSOCIATES, INC.			CONSOLIDATED ESTIMATE		CONDITION I	
MANAGEMENT CONSULTANTS CONSULTING ENGINEERS			CONSTRUCTION MANAGERS			
315 WEST RANDOLPH STREET, CHICAGO, ILLINOIS 60606						
PROJECT EXTERIOR SHIELD-NEW CASTLE - 11 GA.			TYPE OF ESTIMATE BUDGET		ESTIMATE NO. 5128	
LOCATION J. I. T. R. I.			ARCHITECT		DATE 2/18/80	
TAKE OFF BY J.S.			QUANTITIES BY J.S.		PRICES BY J.S.	
EXTENSIONS BY J.S.			CHECKED BY			
CSI CODE	DESCRIPTION	NO.	DIMENSIONS	QUANTITY	UNIT	UNIT
1	PLATE - 11 GA. - 5'x10'			892	EA	55.
2	PLATE - 11 GA. - 5'x10' - RENOVE			45	EA	55.
14	PUNCH WELD PUGH HOLES IN 11 GA. R			10974	EA	10
14	WELD - CONTINUOUS @ 11 GA. R, GRIND FL, EXT. WALLS			16329	L.F.	10
18	WELD PUGH HOLES @ GRIND IN 11 GA. R			3384	EA	.05
18	WELD PUGH HOLES IN 11 GA. R			7590	EA	.05
50	ANGLE - 2" x 2" x 1/8"			2282	L.F.	.50
50	NAILON STRIPS WELD TO 2" x 2" x 1/8" ANGLE			1141	EA	.83
7	DRILL HOLES FOR CONCRETE FORM NAILS @ 2' x 4' x 1/8" ANGLE			1141	EA	
8	INSTALL 2" x 2" x 1/8" ANGLE TO CONC. FORM			2282	L.F.	
10	PLATE - 4" x 1/4"			29616	L.F.	1.25
10	NAILON STRIPS WELD TO 4" x 1/4" PLATE			14808	EA	.83
10	DRILL HOLES FOR CONCRETE FORM NAILS @ 2" x 3" x 1/8" ANGLE			14808	EA	
10	INSTALL 4" x 1/4" PLATE TO CONC. FORM			29616	L.F.	
13	DOOR S			7	EA	
15	PLATE - 11 GA. - 1'W x 520 L.F. (FROM 5'10' SHEETS)			11	EA	75.
15	DRILL HOLES FOR REBAR IN 1'W x 520 L.F. R			1040	EA	
15	REINFORC. RODS - 3'14" x 8"			1040	EA	.70
15	WELD REBAR TO 1'W x 520 L.F. R			1040	EA	.10
15	WELD 1'W x 520 L.F. PLATE TO FLOOR R-GR			520	L.F.	.10
23	PAINT STEEL @ EXT. WALL			11440	S.F.	.10
23	SHIELD PENETRATIONS			27	EA	400.
24	PLATE - 1/4" - 5'x10'			30	EA	112.
24	PUNCH WELD PUGH HOLES IN 1/4" R			360	EA	.12
24	WELD - CONTINUOUS @ 1/4" PLATE			535	L.F.	.16
24	WELD PUGH HOLES @ GRIND IN 1/4" R			360	EA	.15
				145410		
				543680		
						688090



THE ESTERLE KNIGHT & ASSOCIATES, INC.
MANAGEMENT CONSULTANTS CONSULTING ENGINEERS
CONSTRUCTION MANAGERS
330 WEST MADISON STREET, CHICAGO, ILLINOIS 60606

CONSOLIDATED ESTIMATE

CONDITION II

SHEET NO. 1 OF 1

ESTIMATE NO. 5128

DATE 2/20/80

Budget

TYPE OF ESTIMATE

Interior Shield - New Constr. - 11GA

LOCATION I.I.T.R.I.

ARCHITECT

CHECKED BY

EXTENSIONS BY
J. S.

15

PRICES BY

15

QUANTITIES BY

15

1

[illegible]

APPENDIX B

LESTER H. KNIGHT & ASSOCIATES, INC.										CONSOLIDATED ESTIMATE		CONDITION III													
MANAGEMENT CONSULTANTS CONSULTING ENGINEERS										SHEET NO.		OF													
CONSTRUCTION MANAGERS										ESTIMATE NO.															
319 WEST HANDBOLPH STREET, CHICAGO, ILLINOIS 60604										DATE															
PROJECT RETROFIT - INTERIOR SHIELD WITH INSIDE WALLS REMOVED TYPE OF ESTIMATE										BUDGET															
LOCATION 11 GA. SHIELD - CONCRETE EXTERIOR WALLS ARCHITECT L BK & ASSOCIATES										CHECKED BY															
TAKE OFF BY WM										QUANTITIES BY WM		PRICES BY WM		EXTENSIONS BY WM		MATERIAL		LABOR		TOTAL COST					
DESCRIPTION										NO.		DIMENSIONS		UNIT		QUANTITY		UNIT		TOTAL		UNIT		TOTAL	
DEMOLITION OF INTERIOR COMPLETE																11,484		3F		689,010		158.		\$ 689,010	
PLATE 11 GA. 5' x 10'																460		EA		47,380		158.		72,680	
PLATE 11 GA. REWORK 5' x 10'																297		EA		33,565		168.		45,900	
PLATE 11 GA. SHOPFORM 5' x 10'																150		EA		18,600		252.		37,800	
PLATE 11 GA. SHOPFORM - REWORK										5' x 10'						30		EA		40,800		252.		75,600	
PLATE 11 GA. SHOPFORM 6' x 10'																23		EA		31,300		252.		58,000	
PLATE 11 GA. SHOPFORM - REWORK										6' x 10'						23		EA		34,000		252.		57,900	
PUNCH - WELD PLUG HOLES IN 11 GA. PLATE																14,182		EA		1,210,600				1,210,600	
WELD CONTINUOUS AT 11 GA. PLATE										(3,740 GRIND @ 90 DEGREE)						15,132		LF		17,132,592,110				2,607,200	
WELD PLUG HOLES IN 11 GA. PLATE																11,782		EA		590,250		29,455		300,500	
WELD PLUG HOLES & GRIND - 11 GA. PLATE																2,400		EA		120,300		72,000		73,200	
PLATE 4" WIDE x 1/4" THICK																24,258		LF		30,320		65		46,090	
INSTALL 4" x 4" x 1/4" ANGLE																2,200		LF		41,900		60		5,500	
SHOOT IN PLATE ANCHORS TO WALL																14,330		EA		1,430		1,25		17,910	
SHIELD PENETRATIONS (AVG)										1'-4" O.C.						59		EA		23,600		100.		59,000	
CEILING HANGERS WELDED TO SHIELD																7,500		EA		75,000		100.		75,000	
WELD CIRCUMFERENCE OF COLUMN																42		LF		10		17,13		730	
CONCRETE COLUMN COVERS AT BEAM ABUTMENT																7		EA		700,400.		28,000		35,000	
DOORS (HINGED) - SHIELDED																5		EA		10,000		500.		25,000	
DOOR (SLIDING) - SHIELDED																2		EA		12,000		1,000		14,000	
1/4" PLATE 5' x 10'																18		EA		2020		160.		4,900	
1/4" PLATE REWORK 5' x 10'																6		EA		670		180.		1,750	
PUNCH - WELD PLUG HOLES IN 1/4" PLATE																288		EA		35		315		350	
WELD CONTINUOUS AT 1/4" PLATE																440		LF		70		35.		15,470	
WELD PLUG HOLES IN 1/4" PLATE																288		EA		45		3.00		910	

CONSOLIDATED ESTIMATE										CONDITION III	
I. KNIGHT & ASSOCIATES, INC. MANAGEMENT CONSULTANTS CONSULTING ENGINEERS CONSTRUCTION MANAGERS 310 WEST RANDOLPH STREET, CHICAGO, ILLINOIS 60601										SHEET NO. _____ OF _____	
PROJECT RETROFIT - INTERIOR SHIELD WITH INSIDE WALLS REMOVED TYPE OF ESTIMATE <u>BUDGET</u>										ESTIMATE NO. _____	
LOCATION <u>11 GA. SHIELD - CONCRETE EXTERIOR WALLS</u> ARCHITECT <u>LBK & ASSOCIATES</u>										DATE _____	
TAKE OFF BY <u>WM</u> QUANTITIES BY <u>WM</u> PRICES BY <u>WM</u> EXTENSIONS BY <u>WM</u> CHECKED BY _____											
CSI CODE	DESCRIPTION	NO.	DIMENSIONS	UNIT	QUANTITY	UNIT	MATERIAL	UNIT	LABOR	UNIT	TOTAL COST
	INTERIOR FINISHES - CEILINGS - FLOOR WALLS - DOORS				11,484	SF	5.15	59,200	3.39	38,920	\$ 98,120.00
	ELECTRICAL				11,484	SF	1.20	13,780	1.80	20,670	34,450
	ELECTRICAL - SPECIAL SYSTEMS				11,484	SF	3.60	41,340	2.40	27,560	68,900
	HVAC. & PLUMBING				11,484	SF	6.03	69,260	8.97	103,000	172,260
	PERIMETER FINISHES				10,200	SF	.94	9,600	.64	6,520	16,120
	PAINT - INTERIOR FINISHES				76,680	SF	.12	9,120	.22	17,000	26,120
								36,790	77,610	\$ 1,145,510	

J. KNIGHT & ASSOCIATES, INC.				CONSOLIDATED ESTIMATE				CONDITION IIIA			
MANAGEMENT CONSULTANTS CONSULTING ENGINEERS											
CONSTRUCTION MANAGERS											
519 WEST RANDOLPH STREET, CHICAGO, ILLINOIS 60606											
PROJECT RETROFIT - INTERIOR SHIELD WITH INSIDE WALLS REMOVED				TYPE OF ESTIMATE BUDGET							
LOCATION 11 GA. SHIELD - CONCRETE BLOCK EXTERIOR WALLS				ARCHITECT L&K & ASSOCIATES							
TAKE OFF BY WM				EXTENSIONS BY WM				CHECKED BY			
CSI	DESCRIPTION	NO.	DIMENSIONS	UNIT	QUANTITY	UNIT	MATERIAL	UNIT	LABOR	UNIT	TOTAL COST
CODE											
	DEMOLITION OF INTERIOR COMPLETE										
	PLATE 11 GA. 5' x 10'			SF	11,484						68,900
	PLATE 11 GA. REWORK 5' x 10'			EA	460						72,680
	PLATE 11 GA. SHOP FORM 5' x 10'			EA	297						49,900
	PLATE 11 GA. SHOP FORM - REWORK			EA	150						37,800
	PLATE 11 GA. SHOP FORM 6' x 10'			EA	30						7,560
	PLATE 11 GA. SHOP FORM - REWORK			EA	23						5,800
	PUNCH - WELD PLUG HOLES IN 11 GA. PLATE			EA	23						5,790
	WELD CONTINUOUS AT 11 GA. PLATE			EA	14,182						134,500
	WELD PLUG HOLES IN 11 GA. PLATE			EA	15,132						260,720
	WELD PLUG HOLES & GRIND - 11 GA. PLATE			EA	11,782						30,050
	WELD PLUG HOLES 4" WIDE x 1/4" THICK			EA	2,400						7,320
	INSTALL 4" x 4" x 1/4" ANGLE			EA	2,258						46,090
	DRILL 1/2" & COUNTERSINK HOLES @ 2'-0" O.C. IN PLATE			EA	2,200						5,500
	DRILL AND SET MASONRY ANCHORS			EA	14,330						19,340
	SCREW PLATE TO CONCRETE BLOCK WALL			EA	14,330						28,660
	SHIELD PENETRATIONS (AVG.)			EA	14,330						16,480
	CEILING HANGERS WELDED TO SHIELD			EA	59						29,500
	WELD CIRCUMFERENCE OF COLUMNS			EA	7,500						15,000
	CONCRETE COLUMN COVERS @ BEAM ABUTMENT			EA	42						730
	DOORS (HINGED)			EA	7						3,500
	DOOR (SLIDING) - SHIELDED			EA	5						2,500
	1/4" PLATE 5' x 10'			EA	2						1,400
	1/4" PLATE REWORK 5' x 10'			EA	18						4,900
	PUNCH - WELD PLUG HOLES IN 1/4" PLATE			EA	6						1,750
	WELD CONTINUOUS @ 1/4" PLATE			EA	288						3,500
	WELD PLUG HOLES IN 1/4" PLATE			EA	440						15,470
				EA	288						910

[illegible]

APPENDIX B

L. DENTON B. KNIGHT & ASSOCIATES, INC. MANAGEMENT CONSULTANTS CONSULTING ENGINEERS CONSTRUCTION MANAGERS 305 WEST ARNDORPH STREET, CHICAGO, ILLINOIS 60606		CONSOLIDATED ESTIMATE		CONDITION IVA		SHEET NO. OF	
PROJECT RETROFIT - INTERIOR SHIELD		TYPE OF ESTIMATE BUDGET		ESTIMATE NO.		DATE	
LOCATION 11 GA. SHIELD - CONCRETE BLOCK EXTERIOR WALLS ARCHITECT LBG & ASSOCIATES		EXTENSIONS BY WM		CHECKED BY		TOTAL COST	
TAKE OFF BY WM	QUANTITIES BY WM	PRICES BY WM	EXTENSIONS BY WM	QUANTITY	UNIT	LABOR	TOTAL
DESCRIPTION	NO.	DIMENSIONS	UNIT	QUANTITY	UNIT	UNIT	UNIT
DEMOLITION OF INTERIOR - CEILING & LIGHT FIXTURES				11,484	SF	4.50	51,680
PLATE 11 GA 5' x 10' REWORK 5' x 10'				712	EA	103.	73,340
PLATE 11 GA SHOP FORM 5' x 10'				429	EA	113.	48,480
PLATE 11 GA SHOP FORM - REWORK 5' x 10'				150	EA	124.	18,600
PLATE 11 GA SHOP FORM 6' x 10'				30	EA	136.	4,080
PLATE 11 GA. SHOP FORM - REWORK 6' x 10'				23	EA	136.	3,130
PLATE 11 GA. SHOP FORM - REWORK 6' x 10'				23	EA	148.	3,400
PUNCH - WELD PLUG HOLES IN 11 GA. PLATE				18,022	EA	.10	1,802
WELD CONTINUOUS @ 11 GA. PLATE				21,632	LF	.10	2,163
WELD PLUG HOLES & GRIND - 11 GA. PLATE				2,400	EA	.05	120
PLATE 4" WIDE x 1/4" THICK				38,918	LF	1.25	48,650
INSTALL 4" x 4" x 1/4" ANGLE				2,200	LF	1.30	2,860
WELD PLUG HOLES IN 11 GA. PLATE				15,622	EA	.05	781
DRILL 1/2" COUNTERSINK HOLES @ 2'-9" O.C. IN PLATE				21,660	EA	.10	2,166
DRILL & SET MASONRY ANCHORS				21,660	EA	1.00	21,660
SCREW PLATE TO CONCRETE BLOCK WALL				21,660	EA	.15	3,249
CEILING HANGERS WELDED TO SHIELD 1'-4" O.C.				7,500	EA	1.00	7,500
WELD CIRCUMFERENCE OF COLUMNS				42	LF	1.0	42
CONCRETE COLUMN COVERS @ BEAM ABUTMENT				7	EA	100.	700
DOORS (HINGED) - SHIELDED				5	EA	2,000	10,000
DOOR (SLIDING) - SHIELDED				2	EA	6,000	12,000
1/4" PLATE 5' x 10'				18	EA	112.	2,016
1/4" PLATE - REWORK 5' x 10'				6	EA	112.	672
PUNCH - WELD PLUG HOLES IN 1/4" PLATE				288	EA	.12	34.6
WELD CONTINUOUS @ 1/4" PLATE				440	LF	.16	70.4
WELD PLUG HOLES IN 1/4" PLATE				288	EA	.15	43.2
SHIELD PENETRATIONS (AVG)				59	EA	400.	23,600
							59,000

2-29-80

CONDITION V
NEW CONSTRUCTION, INTERIOR SHIELD, POWDER DRIVEN PINS, 14 GA
Budgetary Estimate - IITRI - Feb 1980

Description	Quantity	Unit	Material		Labor		Total Cost
			Unit	Total	Unit	Total	
Galvanized Sheet 14 GA, 48"x96"	1,008	EA	30.00	30,240	27.00	27,216	57,456
Galvanized Sheet 14 GA, 48"x96" formed	364	EA	40.00	14,560	27.00	9,828	24,388
Galvanized Sheet 14 GA, 30"x96" formed	436	EA	40.00	17,440	27.00	11,772	29,212
Fastening Pins	85,000	EA	0.35	29,750			29,750
Grit Blasting of Seams	21,042	LF				7,500	7,500
Shielded Door (Sliding)	2	EA	6,000	12,000	1,000	2,000	14,000
Shielded Door (Hinged)	5	EA	2,000	10,000	500	2,500	12,500
Zinc, Arc Sprayed	9,172	LB	1.34	12,290		12,240	16,658
Ceiling Hangers	7,500	EA	1.00	7,500		4,000	11,500
Plate 1/4" 5'x10'	18	EA	112.00	2,020	160.00	2,880	4,900
Plate 1/4" 5'x10' Rework	6	EA	112.00	670	180.00	1,080	1,750
Punch Weld Holes in 1/4" Plate	288	EA	0.12	40	1.10	320	360
Weld Plug Holes in 1/4" Plate	288	EA	0.15	40	3.00	860	900
Weld Seams, 1/4" Plate	440	LF	0.16	70	35.00	15,400	15,470
4"x1/4" Plate w/Studs & Nail Holes	920	LF	2.01	1,850	2.50	2,300	4,150
Penetrations	59	EA	400.00	23,600	100.00	5,900	29,500
				162,070		105,796	267,866

DISTRIBUTION LIST

DEPARTMENT OF DEFENSE

Assistant Secretary of Defense
Comm., Cmd., Cont. & Intell.
ATTN: Programs & Resources
ATTN: Surveillance & Warning Systems
ATTN: Telecomm. Systems

Assistant Secretary of Defense
Program Analysis & Evaluation
ATTN: General Purpose Programs

Assistant to the Secretary of Defense
Atomic Energy
ATTN: Executive Assistant
ATTN: B. Adams

Command & Control Technical Center
ATTN: C-313

Commander-in-Chief, Pacific
ATTN: J-620

Defense Advanced Rsch. Proj. Agency
ATTN: TIO

Defense Communications Agency
ATTN: WWMCCS Sys. Engr.
ATTN: Code 101B

Defense Communications Agency, Pacific Area
ATTN: Commander

Defense Communications Engineer Center
ATTN: Code R720, C. Stansberry

Defense Intelligence Agency
ATTN: DT

Defense Nuclear Agency
ATTN: NATA
ATTN: RAEV
ATTN: RAAE
ATTN: STNA
2 cy ATTN: RAEE
4 cy ATTN: TITL

Defense Technical Information Center
12 cy ATTN: DD

Field Command
Defense Nuclear Agency
ATTN: FCPR

Field Command
Defense Nuclear Agency
Livermore Division
ATTN: FCPRL

Joint Chiefs of Staff
ATTN: J-3, WWMCCS & Telecommunications
ATTN: J-3
ATTN: SAGA
ATTN: C3S, Evaluation Office
ATTN: J-5, Nuclear Division

DEPARTMENT OF DEFENSE (Continued)

Joint Strat. Tgt. Planning Staff
ATTN: JPST
ATTN: JLTW-2
ATTN: JLA

National Central Sec. Serv., Pacific Area
ATTN: Central Sec. Serv., Pac. Area

National Communications System
ATTN: NCS-TS, D. Bodson

National Security Agency
ATTN: TDL

NET Assessment
Office of the Secretary of Defense
ATTN: Military Assistants

Undersecretary of Def. for Rsch. & Engrg.
ATTN: Strategic & Space Systems (OS)

DEPARTMENT OF THE ARMY

Headquarters
Department of the Army
ATTN: DAMO-TCV-A

Deputy Chief of Staff for Rsch. Dev. & Acq.
Department of the Army
ATTN: DAMA-CSS-N

Harry Diamond Laboratories
Department of the Army
ATTN: DELHD-N-P
ATTN: DELHD-N-RBA
ATTN: DELHD-I-TL
4 cy ATTN: DELHD-N-EM

Multi Service Communications Systems
Department of the Army
ATTN: DRCPM-MSCS-APB, M. Francis

U.S. Army CINCPAC Support Group
ATTN: Communications Electronics Div.

U.S. Army Communications Command
ATTN: CC-OPS-WR

U.S. Army Communications Sys. Agency
ATTN: CCM-AD-LB
ATTN: CCM-RD-T CCM-AD-SV

U.S. Army Computer Systems Command
ATTN: Technical Library

U.S. Army Nuclear & Chemical Agency
ATTN: Library

DEPARTMENT OF THE NAVY

Naval Electronic Systems Command
ATTN: Technical Library
ATTN: PME 117-20

DEPARTMENT OF THE NAVY (Continued)

Naval Ocean Systems Center
ATTN: Code 4471

Naval Postgraduate School
ATTN: Code 0142, Library

Naval Research Laboratory
ATTN: Code 2627

Naval Surface Weapons Center
ATTN: Code F30
ATTN: Code F32

Naval Telecommunications Command
ATTN: Deputy Director Systems

Office of Naval Research
ATTN: Code 715

Office of the Chief of Naval Operations
ATTN: OP 98
ATTN: OP 94

Strategic Systems Project Office
Department of the Navy
ATTN: NSP-43

DEPARTMENT OF THE AIR FORCE

Air Force Communications Service
ATTN: XP

Air Force Geophysics Laboratory
ATTN: SULL

Air Force Security Service
ATTN: XRZ

Air Force Weapons Laboratory
Air Force Systems Command
ATTN: DYC
ATTN: SUL
ATTN: NTO

Assistant Chief of Staff
Studies & Analyses
Department of the Air Force
ATTN: AF/SA

Ballistic Missile Office
Air Force Systems Command
ATTN: MNRTE

Deputy Chief of Staff
Operations Plans and Readiness
Department of the Air Force
ATTN: AFXOK

Deputy Chief of Staff
Research, Development, & Acq.
Department of the Air Force
ATTN: AFRDQ

Foreign Technology Division
Air Force Systems Command
ATTN: NIIS Library

Commander-in-Chief, Pacific Air Forces
ATTN: Communications Electronics

DEPARTMENT OF THE AIR FORCE (Continued)

Headquarters Space Division
Air Force Systems Command
ATTN: SKF

Rome Air Development Center
Air Force Systems Command
ATTN: TSLD

Strategic Air Command
Department of the Air Force
ATTN: XPFS
ATTN: NRI-STINFO Library

OTHER GOVERNMENT AGENCY

Federal Emergency Management Agency
ATTN: Plans & Operations (EO)

DEPARTMENT OF DEFENSE CONTRACTORS

American Telephone & Telegraph Co.
ATTN: M. Gray for W. Edwards

BDM Corp.
ATTN: L. Jacobs

Boeing Co.
ATTN: V. Jones
2 cy ATTN: H. Hendrickson

Computer Sciences Corp.
ATTN: H. Blank

ESL, Inc.
ATTN: J. Marshall

General Electric Company—TEMPO
ATTN: OASAC

GTE Sylvania, Inc.
ATTN: M. Cross
ATTN: E. Motchok

Institute for Defense Analyses
ATTN: Classified Library

IRT Corp.
ATTN: R. Wheeler
ATTN: O. Swift
ATTN: L. Duncan

R & D Associates
ATTN: B. Gage
ATTN: W. Graham, Jr.
ATTN: R. Schaefer
ATTN: C. MacDonald
ATTN: P. Haas

R & O Associates
ATTN: J. Bombardt

SRI International
ATTN: A. Whitson
ATTN: G. Carpenter

IIT Research Institute
ATTN: T. Martin